STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10 - RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 4.380, RT	A	W1-2 L	36	36								X		X											REMOVE SIGN AND POST			
		A	W10-1L	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 364 FT SOUTH OF THE CENTER OF MAYO R)	X		
		A	W16-8P	24	8		Mayo Rd	1.33																		INSTALL NEW SIGN BENEATH HORIZONTAL ALIGNMENT WITH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		10	
SB	MM 4.380, LT	F	TOWN SIGN	30	30								X		X											REMOVE SIGN AND POST			
SB	MM 4.390, LT TO MM 4.440, LT	F E		6	8		(6) TYPE II - 6" X 8" WHITE DELINEATORS	2.00								3	X									INSTALL DELINEATORS BACK-TO-BACK (6 TOTAL) 70 FT APART GOING SOUTH, INSTALL FIRST ONE AT POLE #107		7	
							HINESBURG RD																						
EB	MM 3.782, RT	A	W3-1	30	30								X		X											REMOVE SIGN AND POST			
EB	MM 3.823, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 260 FT EAST OF POLE# 113868 3 4	X		
EB	MM 3.842, RT	A	D1-1	36	6		HUNTINGTON →			X	1			X												RETAIN SIGN AND 2-POSTS			
		A	D1-1	36	6		← ROUND CHURCH			X	1															RETAIN SIGN BENEATH HUNTINGTON (TOWN SIGN) ON THE SAME POSTS			
		A	D1-1	32	6		← RICHMOND			X	1			X												RETAIN SIGN BENEATH ROUND CHURCH (TOWN) SIGN ON THE SAME POSTS			
EB	MM 3.885, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE EXISTING STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION (HUNTINGTON RD INTERSECTION)	X		
		A	D3-1	36	6		Hinesburg Rd						X													REMOVE SIGN			
		A	D3-1	36	6		Huntington Rd						X													REMOVE SIGN			
		A	D3-1	42	12		Hinesburg Rd	3.50																		INSTALL NEW SIGN ABOVE THE NEW HUNTINGTON RD SIGN ON THE SAME POST		10	
		A	D3-1	48	12		Huntington Rd	4.00								1		X								INSTALL NEW SIGN AND POST 5 FT EAST OF THE STOP SIGN		10	
										EA 3	EA 3	EA	EA 7	EA 2	EA 5		FT 24	FT 90	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 35.08	SF	EA ~~10~~ 7				EA ~~7~~		EA ~~9~~	FT 114			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 10
PLOT DATE: 14-SEP-2012 15:30
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 39 OF 51