STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 – ST. ALBANS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.595, LT	F	W13-1P	18	18		25 M.P.H.						~~X~~													REMOVE SIGN			
NB	MM 1.844, RT	A	W1-5	30	30								X		X											REMOVE SIGN AND POST			
		A	W13-1P	18	18		25 M.P.H.						X													REMOVE SIGN			
		A	W1-4	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 5 FT SOUTH OF POLE# 16/NET/6			
NB	MM 1.886, RT TO MM 1.9525, RT	A/B		6	8		(12) TYPE II - 6" X 8" WHITE DELINEATORS	4.00								6 @7.5 EA.	X									INSTALL DELINEATORS BACK-TO-BACK 70 FT APART. INSTALL FIRST DELINEATOR 75 FT NORTH OF AND ACROSS FROM POLE# 41/1/4415		7	
NB	MM 1.898, RT	A	VN-054	30	30		HIDDEN DRIVES RIGHT	6.25								1		X								INSTALL NEW SIGN AND POST 120 FT SOUTH OF AND ACROSS FROM POLE# 4/3/13		8	
NB	MM 1.931, RT	A	VR-072 VR-072	24 24	30 30		THINK B-B THINK			X X				X												RETAIN BACK-TO-BACK ENCARE SIGNS AND POST			
SB	MM 1.985, LT	F	TOWN SIGN	18	24		SLOW CHILDREN						~~X~~		~~X~~											REMOVE SIGN AND POST			
SB	MM 2.029, LT	F	W1-5	30	30								X		X											REMOVE SIGN AND POST			
		F	W13-1P	18	18		25 M.P.H.						X													REMOVE SIGN			
		F	W1-4	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 280 FT NORTH OF AND ACROSS FROM POLE# 12	X		
NB	MM 2.394, RT	A	W3-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 137 FT SOUTH OF POLE# 413/2	X		
SB	MM 2.425, LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 26 FT NORTH OF AND ACROSS FROM POLE# 413/2	X		
		F	R2-1	24	30		SPEED LIMIT 40	5.00																		INSTALL NEW SIGN BENEATH THE LEGAL LOAD LIMIT SIGN ON THE SAME POST	X		
SB	MM 2.455, LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X											REMOVE SIGN AND POST			
NB	MM 2.459, RT	A	R1-1	30	30		STOP			X				X												RETAIN EXISTING SIGN AND POST	X		
										EA 3	EA	EA	EA ~~9~~ 8	EA 2	EA 6		FT 48	FT 90	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF ~~35.50~~ 41.75	SF	EA ~~12~~ 8				EA ~~8~~		EA ~~12~~	FT 138			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 14-SEP-2012 15:31
DRAWN BY: ITS
CHECKED BY: JLS