STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – ST. ALBANS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.462, LT	F	D3-1	36	6		Lower Newton Rd						X		X											REMOVE SIGN AND POST			
SB		G	D3-1	30	6		Kellogg Rd						X		X											REMOVE SIGN			
NB	MM 2.475, RT	C	D3-1	36	12		Kellogg Rd	3.00					~~X~~		~~X~~											INSTALL NEW SIGN ABOVE LOWER KELLOGG RD STREET NAME SIGN ON SAME POSTS		II	
NB		A	D3-1	54	12		Lower Newton Rd	4.50								2		X								INSTALL NEW SIGN ON 2-POSTS 5 FT TO THE RIGHT OF RETAINED STOP SIGN WITHOUT OBSTRUCTING STOP SIGN'S VISIBILITY		II	
NB	MM 2.476, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X											REMOVE SIGN AND POST			
SB	MM 2.476, LT	F	RI-1	30	30		STOP			X				X												RETAIN STOP SIGN AND POST			
NB	MM 2.487, RT	A	TOWN SIGN	18	24		SLOW CHILDREN						X													REMOVE SIGN			
NB	MM 2.487, RT	A	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 275 FT SOUTH OF AND ACROSS FROM POLE# 412/2	X		
NB		A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		INSTALL NEW SIGN ABOVE THE 30 MPH SPEED LIMIT SIGN ON SAME POST	X		
SB	MM 2.542, LT	F	W3-1	36	36			9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 16 FT NORTH OF AND ACROSS FROM POLE# 412/2	X		
NB	MM 2.673, RT	A	W11-4	30	30								X		X											REMOVE SIGN AND POST			
SB	MM 2.740, LT	F	W11-4	30	30								X		X											REMOVE SIGN AND POST			
SB	MM 2.878, LT	F	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 148 FT SOUTH OF THE CENTER OF JEWETT AVENUE	X		
SB	MM 2.906, LT	G	W1-7	48	24					X				X X												RETAIN SIGN AND 2-POSTS			
NB	MM 2.912, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (JEWETT AVENUE)	X		
NB		A	D3-1	36	12		Jewett Ave	3.00																		INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST		II	
										EA 2	EA	EA	EA ~~11~~ 10	EA 3	EA 10			FT 105	FT			LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 40.75	SF	EA			~~13~~ 10	EA	~~13~~	EA ~~7~~		FT 105		EA		LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 14-SEP-2012 15:31
DRAWN BY: ITS
CHECKED BY: JLS
ST. ALBANS TRAFFIC SIGN SUMMARY SHEET 3 SHEET 43 OF 51