STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – TOWN TOTALS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							ENOSBURG TOTAL TSS SHEET	~~186.30~~ 181.719					~~29~~ 28		~~24~~	~~36~~		~~540~~ 480.5											
							FERRISBURGH TOTAL TSS SHEET	~~277.16~~ 282.16					~~23~~ 25		~~16~~	~~54~~		~~810~~ 754.5											
							NEW HAVEN TOTAL TSS SHEET	171.21		~~3~~			~~18~~ 19	~~2~~	~~18~~	~~54~~	~~176~~	~~480~~ 633											
							NORTHFIELD TOTAL TSS SHEET	87.25					13		~~10~~	~~22~~	~~56~~	~~225~~ 280											
							RICHMOND TOTAL TSS SHEET	585.09		~~5~~			~~77~~ 82	~~4~~	~~54~~	~~115~~	~~160~~	~~1425~~ 1487											
							ST. ALBANS TOWN TOTAL TSS SHEET	~~148.25~~ 159.5		~~6~~			~~36~~ 33	~~6~~	~~31~~	~~32~~	~~48~~	~~390~~ 403.5											
							WEYBRIDGE TOTAL TSS SHEET	39.50		~~2~~			4		~~5~~	~~9~~		~~135~~ 121											
							PROJECT GRAND TOTALS	SF ~~1494.76~~ 1506.429	SF	EA ~~16~~	EA 3	EA	EA ~~200~~	EA ~~12~~	EA ~~158~~	EA ~~322~~	FT ~~440~~	FT ~~4005~~	FT	EA	LB	LB	LB	LB				
													EA ~~216~~ 204		EA ~~170~~													

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
TOWN TOTAL SIGN SUMMARY SHEET

PLOT DATE: 14-SEP-2012 15:31
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 47 OF 51