STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - ENOSBURG

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.336, LT	F	TOWNSIGN	30	30		ONE LANE ROAD AHEAD						X		X											REMOVE SIGN AND POST			
SB		F	R2-1	24	30		SPEED LIMIT 10						X													REMOVE SIGN			
SB	MM 0.346, LT	F	R1-2	36	36		YIELD						X		X											REMOVE SIGN AND POST			
		F	W2-1	30	30			6.25					X		X	1		X								INSTALL NEW SIGN ON POST 90 FT SOUTH OF POLE# 3	X		
		F	W16-8P	42	8		Tyler Branch Rd	2.33																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 0.359, RT	A	G20-2	36	18		END ROAD WORK						X		X											REMOVE SIGN AND POST			
		A	W1-4R	30	30			6.25					X		X	1		X								INSTALL SIGN AND POST 21FT SOUTH OF POLE# 3	X		
SB	MM 0.363, LT	E F	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SINGLE POST 185 FT SOUTH OF POLE# E/5/4A	X X		
SB	MM 0.381, LT	E F	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SINGLE POST 90 FT SOUTH OF POLE# E/5/4A	X X		
NB	MM 0.398, RT	A	W1-2	30	30								X		X											REMOVE SIGN AND POST			
SB	MM 0.399, LT	E F	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SINGLE POST 5 FT NORTH OF POLE# E/5/4A	X X		
SB	MM 0.404, LT	F	W20-1	36	18		ROAD WORK AHEAD						X		X X											REMOVE SIGN AND 2-POSTS			
NB	MM 0.444, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SINGLE POST 53 FT NORTH OF POLE# 45/5	X X		
NB	MM 0.461, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SIGNLE POST 37 FT SOUTH OF POLE# 158	X X		
NB	MM 0.478, RT	A B	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL CHEVRONS BACK-TO-BACK ON SIGN BRACKET AND SINGLE POST 26 FT NORTH OF THE CENTER OF DRIVE# 3859	X X		
										EA	EA	EA	EA 8	EA	EA 8		FT	FT 120	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 50.83	SF	EA 8				EA 8		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ENOSBURG TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 17-SEP-2012 11:31
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 14 OF 51