

TRAFFIC SIGN SUMMARY SHEET 2 - NEW HAVEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			FOUNDAION						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
SB	MM 0.118, LT	F	W5-3	36	36			9.00					X		X	2		X						INSTALL NEW SIGN ON 2-POSTS 200 FT NORTH OF NEWLY INSTALLED YIELD AHEAD SIGN ASSEMBLY	X			
		F	TOWN SIGN	24	30								X											REMOVE SIGN				
SB	MM 0.156, LT	F	WI-3 R	30	30			6.25								1		X						INSTALL NEW SIGN AND POST 200 FT NORTH OF NEWLY INSTALLED "ONE LANE BRIDGE" ASSEMBLY	X			
		F	WI3-IP	18	18			2.25																INSTALL BENEATH CURVE WARNING SIGN AT THE CORRECT SIGN HEIGHT	X			
NB	MM 0.170, RT TO MM 0.210, RT	A/B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS	2.67								4	X							INSTALLED BACK-TO-BACK AT 70 FT± SPACING BEGINING 1679 FT SOUTH THE CENTER OF TWITCHELL HILL ROAD INTERSECTION			7	
SB	MM 0.170, LT TO MM 0.210, LT	E/F		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS	2.67								4	X							INSTALLED BACK-TO-BACK AT 70 FT± SPACING BEGINING 1679 FT SOUTH OF THE CENTER OF TWITCHELL HILL RD INTERSECTION			7	
SB	MM 0.283, LT	F	WI-3 R	30	30								X		X									REMOVE SIGN AND POST				
		F	WI3-IP	18	18								X											REMOVE SIGN PLAQUE				
SB	MM 0.283, LT	F	WI-8R	18	24								X		X									REMOVE SIGN AND POST				
SB	MM 0.436, LT	F	W5-3	36	36			9.00								2		X						INSTALL NEW SIGN ON 2-POSTS 275 FT SOUTH OF THE CENTER OF THE TWITCHELL HILL ROAD INTERSECTION	X			
		F	WI6-3AP	30	12			2.50																INSTALL BENEATH ONE LANE BRIDGE SIGN AT THE CORRECT SIGN HEIGHT	X			
SB	MM 0.478, LT	F	R2-1	24	30		RESET 10-21-11	5.00					X		X	1		X						INSTALL NEW SIGN AND POST 75 FT SOUTH OF THE CENTER OF THE TWITCHELL HILL ROAD INTERSECTION	X			
		F	TOWN SIGN	30	36								X											REMOVE SIGN				
SB	MM 0.482, LT	H	RI-1	30	30			6.25					X		X	1		X						REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X			
NB	MM 0.513, RT	A	R2-1	24	30			5.00					X		X	1		X						INSTALL NEW SIGN AND POST 1236 FT SOUTH OF POLE# 408/2/1	X			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

			EA	EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB
						9		6			64	120						
SF	SF		EA	EA	EA		EA	EA			FT			EA		LB		
50.59			9				-6	-6			184							

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn PLOT DATE: 17-SEP-2012 11:32
PROJECT LEADER: JLS DRAWN BY: ITS
DESIGNED BY: NLA CHECKED BY: JLS
NEW HAVEN TRAFFIC SIGN SUMMARY SHEET 2 SHEET 24 OF 51