STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 – NEW HAVEN

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 0.513, RT	A	W2-2 R	30	30			6.25					X		X	I		X								INSTALL NEW SIGN AND POST 1236 FT SOUTH OF POLE# 408/2/1	X		
		A	W16-8P	36	8			2.00																		INSTALL BENEATH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
SB	MM 0.791, LT	F	R2-1	24	30			5.00					X		X	I		X								INSTALL NEW SIGN AND POST 1236 FT SOUTH OF POLE# 408/2/1	X		
SB	0.837, LT	G	W1-7	48	24			8.00					I			2		X								INSTALL NEW SIGN ON 2-POSTS DIRECTLY ACROSS FROM THE INTERSECTION WITH CAMPGROUND ROAD	X		
NB	MM 0.862, RT	A	R2-1	24	30			5.00					X		X	I		X								INSTALL NEW SIGN AND POST 364 FT SOUTH OF POLE# 4/34	X		
SB	MM 0.903, LT	F	W2-2 L	30	30			6.25					X		X	I		X								INSTALL NEW SIGN AND POST 148 FT SOUTH OF AND ACROSS FROM POLE# 4/34	X		
		F	W16-8P	36	8			2.00																		INSTALL BENEATH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
							CAMPGROUND ROAD																						
EB	STA 0+15, RT	A					EMPTY POST								X											REMOVE POST			
EB	STA 0+52, RT	A					EMPTY POST								X											REMOVE POST			
WB	STA 0+79, LT	F	R1-2	36	36			3.89								I		X								INSTALL NEW SIGN ON 2-POSTS 224 FT WEST OF AND ACROSS FROM POLE# 3	X		
EB	STA 1+08, RT	A	R2-1	24	30			5.00					X		X	I		X								INSTALL NEW SIGN AND POST 195 FT WEST OF POLE# 3	X		
WB	STA 4+40, LT	F	W3-2A	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 137 FT EAST OF AND ACROSS FROM POLE# 3	X		
							TWITCHELL HILL ROAD																						
WB	STA 0+99, LTT	A	R2-1	24	30			5.00					X		X	I		X								INSTALL NEW SIGN AND POST 99 FT WEST OF THE PEARSON RD INTERSECTION WITH TWITCHELL HILL RD	X		
EB	STA 3+62, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2- POSTS 362 FT WEST OF THE INTERSECTION OF PEARSON RD ON THE SOUTH (RIGHT) SIDE OF TWITCHELL HILL RD	X		
										EA	EA	EA	EA ~~6~~ 7	EA	EA 8		FT	FT 195	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 66.39	SF	EA ~~6~~ 7				EA ~~8~~		EA ~~13~~	FT 195			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 17-SEP-2012 11:32
DRAWN BY: ITS
CHECKED BY: JLS