STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.263, LT	F	D2-1	72	12		Huntington 6 ~~9~~	6.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS END OF SIDEWALK IN FRONT OF THE UTILITY POLE		11	
		F	D2-1	72	12		Hinesburg 9 ~~6~~	6.00					X													INSTALL NEW SIGN BENEATH THE HUNTINGTON DESTINATION SIGN ON THE SAME POSTS		11	
NB	MM 0.266, RT	A	W1-1McL	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 232 FT SOUTH OF THE THOMPSON RD INTERSECTION		11	
		A	W16-8aP	48	15		Thompson Rd Cochran Rd	5.00																		INSTALL NEW SIGN BENEATH TURN/INTERSECTION SIGN AT THE CORRECT SIGN HEIGHT		10	
NB	MM 0.335, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (FARR RD)	X		
		A/B	D3-1	24	12		Farr Rd	2.00					X													INSTALL NEW SIGN ABOVE THE STOP SIGN ON THE SAME POST		10	
NB	MM 0.446, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST ACROSS FROM POLE# 11542	X		
		A	TOWN SIGN	24	30		SPEED CHECK BY RADAR						X													REMOVE SIGN			
SB	MM 0.446, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST IN FRONT OF POLE# 11542	X		
NB	MM 0.465, RT	A	W2-2	30	30			6.25								1		X								INSTALL NEW SIGN 585 FT SOUTH OF FARR RD	X		
		A	W16-8P	24	8		Farr Rd	1.33																		INSTALL NEW SIGN BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		10	
NB	MM 0.553, RT	A	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
		A	W3-5	36	36		SPEED LIMIT 25	9.00								2		X								REMOVE "REDUCE SPEED AHEAD" SIGN AND INSTALL NEW DIAMOND SIGN AND POSTS AT THE SAME LOCATION (ABOUT 560 FT SOUTH OF AND OPPOSITE POLE #11542)	X		
SB	MM 0.583, LT	F	W11-2	30	30								X		X											REMOVE SIGN AND POST			
		F	TOWN SIGN	30	15		PED XING						X													REMOVE SIGN			
							SHEET SUBTOTALS	SF 60.83	SF	EA 9				EA ~~5~~		EA ~~10~~		FT 150		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 2
PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 31 OF 51