STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.612, LT	F	W1-3R	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 5 FT SOUTH OF AND ACROSS FROM POLE# 1	X		
		F	TOWN SIGN	24	24								X													REMOVE SIGN			
		F	W13-1P	18	18			2.25																		INSTALL NEW SIGN BENEATH REVERSE TURN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.630, RT	A B	W1-8 R W1-8 L	18 18	24 24			3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON SIGN BRACKET ON A SINGLE POST 246 FT NORTH OF POLE# 11550	X X		
NB	MM 0.650, RT	A B	W1-8 R W1-8 L	18 18	24 24			3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SIGNLE POST 146 FT NORTH OF POLE# 11550	X X		
NB	MM 0.678, RT	A	W11-2	30	30								X		X											REMOVE SIGN AND POST			
		A	TOWN SIGN	30	15								X													REMOVE SIGN			
SB	MM 0.698, LT	F	W1-2L	30	30								X		X											REMOVE SIGN AND POST			
		F	W1-1L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 100 FT SOUTH AND OPPOSITE OF POLE# 11550	X		
SB	MM 0.737, LT	E	W1-8 R	18	24								X		X											REMOVE SIGN AND POST			
		E	OM-1	18	18								X		X											REMOVE SIGN AND POST			
SB	MM 0.737, LT	F E	W1-8 L W1-8 R	18 18	24 24	F-Y		3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 206 FT SOUTH OF NEWLY INSTALLED CURVE LEFT WARNING SIGN - SAME LOCATION A REMOVED SINGLE CHEVRON SIGN ASSEMBLY	X X		
SB	MM 0.758, LT	F E	W1-8 L W1-8 R	18 18	24 24	F-Y		3.00 3.00					X X		X	1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SINGLE POST 111FT SOUTH OF PREVIOUSLY INSTALLED CHEVRON ASSEMBLY - SAME LOCATION AS REMOVED ASSEMBLY	X X		
SB	MM 0.758, LT	F E	OM-1 OM-1	18 18	18 18								X X		X											REMOVE SIGN AND POST			
SB	MM 0.781, LT	F E	W1-8 L W1-8 R	18 18	24 24	F-Y		3.00 3.00					X X		X	1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SINGLE POST 121FT SOUTH OF PREVIOUSLY INSTALLED CHEVRON ASSEMBLY - SAME LOCATION AS REMOVED ASSEMBLY	X X		
SB	MM 0.804, LT	F	W1-8 L	18	24								X		X											REMOVE SIGN AND POST			
										EA	EA	EA	EA ~~14~~ 15	EA	EA 9		FT	FT 105	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 44.75	SF	EA ~~14~~ 15				EA ~~9~~		EA ~~7~~	FT 105			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 32 OF 51