STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 – RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.971, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST ABOUT 79 FT SOUTH OF THE CENTER OF THE HINESBURG RD INTERSECTION	X		
SB	MM 0.997, LT	F	W1-2 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 50 FT NORTH OF POLE# 56-20	X		
SB	MM 1.021, LT TO MM 1.165, LT	F		6	8		(24) TYPE II - 6" X 8" WHITE DELINEATORS	8.00								12	X									INSTALL 12 DELINEATORS BACK-TO-BACK (24 TOTAL) 70 FT APART GOING SOUTH. INSTALL THE FIRST ONE 36 FT SOUTH OF THE END OF THE FIRST GUARDRAIL OR 84 FT NORTH OF THE OTHER BUSINESS SIGNS (OWL'S HEAD BERRY FARM, BIRDS EYE BUILDING CO)		7	
SB	MM 1.147, LT	F	W2-3R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 200 FT NORTH OF THE CENTER OF HILLVIEW RD	X		
		F	W16-8P	30	8		Hillview Rd	1.67																		INSTALL BENEATH MODIFIED SIDE ROAD INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		10	
SB	MM 1.190, LT	E/F	D3-1	36	12		Hillview Rd	3.00					X		X											INSTALL NEW SIGN ABOVE HUNTINGTON RD STREET NAME SIGN ON SAME POST		10	
		G/H	D3-1	48	12		Huntington Rd	4.00					X													INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST		10	
SB	MM 1.190, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT A LOCATION 10 FT WEST OF THE CURRENT LOCATION (HILLVIEW RD)	X		
SB	MM 1.190, LT +359 FT	H	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS ON HILLVIEW ROAD, ABOUT 359 FT FROM THE INTERSECTION AND 33 FT WEST OF POLE# 119600 2	X		
SB	MM 1.217, LT	F	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN AND POST			
SB	MM 1.223, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 168 FT SOUTH OF THE CENTER OF HILLVIEW RD	X		
NB	MM 1.233, RT	A	W2-3L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 200 FT SOUTH OF THE CENTER OF HILLVIEW RD	X		
		A	W16-8P	30	8		Hillview Rd	1.67																		INSTALL NEW SIGN BENEATH THE MODIFIED SIDE ROAD INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT.		10	
SB	MM 1.486, LT	F	W2-2	30	30								X		X											REMOVE SIGN AND POST			
NB	MM 1.529, RT	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN AND POST			
							SHEET SUBTOTALS	SF 62.34	SF				EA 7		EA ~~6~~	EA ~~20~~			FT 216		EA				LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 5
PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 34 OF 51