STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 8 – RICHMOND

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHS = STANDARD HIGHWAY SIGN BOOK | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| SB | MM 3.344, LT | E/F | D3-1 | 36 | 12 | | Hillview Rd | 3.00 | | | | | X | | | 1 | | X | | | | | | | | INSTALL NEW SIGN ABOVE HUNTINGTON ROAD STREET NAME SIGN ON SAME POST | | 10 | |
| | | G/H | D3-1 | 48 | 12 | | Huntington Rd | 4.00 | | | | | X | | | | | | | | | | | | | INSTALL NEW SIGN ABOVE STOP SIGN ON THE SAME POST | | 10 | |
| | | H | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1 | | X | | | | | | | | REMOVE STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION AS THE PREVIOUSLY REMOVED STREET NAME SIGN ASSEMBLY CLOSER TO THE INTERSECTION | X | | |
| SB | MM 3.350, LT | F | W1-8 L | 18 | 24 | | B-B | 3.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 116 FT SOUTH OF POLE# 77/755 | X | | |
| | | E | W1-8 R | 18 | 24 | | | 3.00 | | | | | | | | | | | | | | | | | | | X | | |
| SB | MM 3.373, LT | F | W1-8 L | 18 | 24 | | B-B | 3.00 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 232 FT SOUTH OF POLE# 77/755 | X | | |
| | | E | W1-8 R | 18 | 24 | | | 3.00 | | | | | | | | | | | | | | | | | | | X | | |
| SB | MM 3.432, LT | F | R2-1 | 24 | 30 | | SPEED LIMIT 45 | 5.00 | | | | | X | | X | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST 220 FT SOUTH OF HILLVIEW ROAD | X | | |
| NB | MM 3.457, RT | A | W10-1R | 36 | 36 | | | 9.00 | | | | | X | | X | 2 | | X | | | | | | | | INSTALL NEW SIGN ON 2-POSTS 353 FT SOUTH OF THE CENTER OF HILLVIEW RD | X | | |
| | | A | W16-8P | 30 | 8 | | Hillview Rd | 1.67 | | | | | | | | | | | | | | | | | | INSTALL NEW SIGN BENEATH HORIZONTAL ALIGNMENT WITH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT | | 10 | |
| SB | MM 3.551, LT | F | W1-5L | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW WINDING ROAD SIGN AND POST AT POLE # 85 | X | | |
| NB | MM 3.739, RT | A | R2-1 | 24 | 30 | | SPEED LIMIT 45 | | | | | | X | | X | | | | | | | | | | | REMOVE SIGN AND POST | | | |
| SB | MM 3.739, LT | F | W10-1R | 36 | 36 | | | 9.00 | | | | | | | | 2 | | X | | | | | | | | INSTALL NEW SIGN ON 2-POSTS 375 FT NORTH OF AND ACROSS FROM THE CENTER OF DUGWAY RD INTERSECTION | X | | |
| | | F | W16-8P | 30 | 8 | | Dugway Rd | 1.67 | | | | | | | | | | | | | | | | | | INSTALL NEW SIGN BENEATH HORIZONTAL ALIGNMENT WITH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT | | 10 | |
| NB | MM 3.747, RT | A | W1-5R | 30 | 30 | | | 6.25 | | | | | | | | 1 | | X | | | | | | | | INSTALL NEW SIGN AND POST OPPOSITE HOUSE# 3420 | X | | |
| NB | MM 3.799, RT | D | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1 | | X | | | | | | | | REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (DUGWAY RD) | X | | |
| | | A/B | D3-1 | 36 | 12 | | Dugway Rd | 3.00 | | | | | | | | | | | | | | | | | | INSTALL SIGN ABOVE THE STOP SIGN ON THE SAME POST | | 10 | |
| NB | MM 3.847, RT | A | W10-1L | 36 | 36 | | | 9.00 | | | | | | | | 2 | | X | | | | | | | | INSTALL NEW SIGN ON 2-POSTS 200 FT SOUTH OF THE CENTER OF DUGWAY RD | X | | |
| | | | | | | | | | | | | | | | | EA | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | EA | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | EA | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | EA ~~7~~ 8 | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | EA ~~5~~ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | EA ~~13~~ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | FT 195 | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | EA | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | LB | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

| SHEET SUBTOTALS | SF 82.34 | SF | EA ~~7~~ 8 | EA ~~5~~ | EA ~~13~~ | FT 195 | EA | LB |
|---|---|---|---|---|---|---|---|---|

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 8

PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 37 OF 51