STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9 – RICHMOND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		A	W16-8P	30	8		Dugway Rd	1.67																		INSTALL NEW SIGN BENEATH THE HORIZONTAL ALIGNMENT WITH SIDE ROAD WARNING SIGN LISTED ON THE PREVIOUS PAGE AT THE CORRECT SIGN HEIGHT		10	
SB	MM 4.006, LT	F	W5-2	36	36		NARROW BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 175 FT NORTH OF THE BEGINNING OF THE BRIDGE	X		
SB	MM 4.040, LT	F	OM3-R	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE NORTH END OF THE BRIDGE ON THE RIGHT HAND SIDE	X		
NB	MM 4.400, RT	A	OM3-L	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE NORTH END OF THE BRIDGE ON THE LEFT HAND SIDE	X		
SB	MM 4.112, LT	E	OM3-L	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE SOUTH END OF THE BRIDGE ON THE RIGHT HAND SIDE (SIGN FACING NORTHBOUND TRAFFIC)	X		
NB	MM 4.112, RT	B	OM3-R	12	36			3.00								1		X								INSTALL OBJECT MARKER AT THE SOUTH END OF THE BRIDGE ON THE LEFT HAND SIDE (SIGN FACING NORTHBOUND TRAFFIC)	X		
NB	MM 4.145, LT	A	W5-2	36	36		NARROW BRIDGE	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 175 FT SOUTH OF THE END OF THE BRIDGE	X		
SB	MM 4.283, LT	F	W10-1R	36	36			9.00								2		X								INSTALL NEW CURVE/INTERSECTION SIGN AND POSTS 150 FT NORTH OF THE CENTER OF MAYO RD	X		
SB	MM 4.283, LT	F	W16-8P	24	8		Mayo Rd	1.33																		INSTALL BELOW THE NEW CURVE/INTERSECTION SIGN		10	
NB	M 4.303, RT	B A	W1-8 L W1-8 R	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 10 FT NORTH OF THE STOP SIGN FOR MAYO RD	X X		
NB	MM 4.305, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X							★	REMOVE STOP SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION (MAYO RD)	X		
NB	MM 4.322, RT	A/B	D3-1	30	12		Mayo Rd	2.50					X		X	1		X							★	INSTALL SIGN ABOVE NEW HUNTINGTON RD STREET NAME SIGN AT THE SAME LOCATION BEHIND GUARDRAIL		10	
NB	MM 4.322, RT	C/D	D3-1	48	12		Huntington Rd	4.00																		INSTALL NEW SIGN BENEATH MAYO RD SIGN ONTHE SAME POST AT THE SAME LOCATION BEHIND GUARDRAIL ACROSS FROM STOP SIGN ON MAYO RD		10	
NB	MM 4.326, RT	B A	W1-8 W1-8	18 18	24 24		B-B	3.00 3.00								1		X								INSTALL NEW CHEVRONS BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 120 FT SOUTH OF THE PREVIOUS PAIR INSTALL 10 FT NORTH OF THE STOP SIGN FOR MAYO RD	X X		
SB	MM 4.361, LT	F	W1-2 L	30	30			6.25								1		X								REMOVE SIGN AND POST			
										EA	EA	EA	EA ~~2~~ 6	EA	EA 2			FT 225				LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 73.00	SF	EA ~~2~~ 6				EA ~~2~~		EA ~~15~~		FT 225		EA		LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RICHMOND TRAFFIC SIGN SUMMARY SHEET 9

PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 38 OF 51