STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – ST. ALBANS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.011, LT	E	D3-1	24	6		Lake St						X		X											REMOVE SIGN AND POST			
		G	D3-1	30	6		Kellogg Rd						X													REMOVE SIGN			
SB	MM 0.015, LT	F	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
		E/F	D3-1	30	12		Lake St	2.50																		INSTALL NEW SIGN ABOVE THE STOP SIGN ON THE SAME POST		II	
		G/H	D3-1	36	12		Kellogg Rd	3.00																		INSTALL NEW SIGN ABOVE THE LAKE ST STREET NAME SIGN		II	
NB	MM 0.029, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS			X				X												RETAIN SIGN AND POST 150 FT NORTH OF THE CENTER OF LAKE ST			
NB	MM 0.060, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 215 FT SOUTH OF POLE# 7/8	X		
SB	MM 0.087, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 75 SOUTH OF POLE# 7/8	X		
SB	MM 0.769, LT	F	TOWN SIGN	12	18		SLOW CHILDREN						~~X~~		~~X~~											REMOVE SIGN AND POST			
SB	MM 1.149, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 15 FT NORTH OF POLE# 29	X		
NB	MM 1.223, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 400 FT NORTH OF POLE# 29	X		
NB	MM 1.395, RT	A	W1-2R	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 495 FT SOUTH OF POLE# 29	X		
		A	W13-1P	18	18		25 M.P.H.						X													REMOVE SIGN			
NB	MM 1.485, RT	A					EMPTY POST								X											REMOVE POST			
NB	MM 1.504, RT	A					EMPTY POST								X											REMOVE POST			
SB	MM 1.595, LT	F	W1-2L	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 575 FT NORTH OF POLE# 29	X		
										EA 1	EA	EA	EA ~~10~~ 9	EA 1	EA 10		FT	FT 120	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 48.25	SF	EA ~~11~~ 9				EA ~~11~~		EA ~~8~~		FT 120		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ST. ALBANS TRAFFIC SIGN SUMMARY SHEET 1
PLOT DATE: 17-SEP-2012 11:33
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 41 OF 51