

TRAFFIC SIGN SUMMARY SHEET 2 - ST. ALBANS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDATION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
SB	MM 1.595, LT	F	WI3-IP	18	18																		REMOVE SIGN					
NB	MM 1.844, RT	A	WI-5	30	30								X		X									REMOVE SIGN AND POST				
		A	WI3-IP	18	18								X											REMOVE SIGN				
		A	WI-4	30	30			6.25							I		X							INSTALL NEW SIGN AND POST 5 FT SOUTH OF POLE# 16/NET/6				
NB	MM 1.886, RT TO MM 1.9525, RT	A/B		6	8		(12) TYPE II- 6" X 8" WHITE DELINEATORS	4.00							6 @ 7.5 EA.	X								INSTALL DELINEATORS BACK-TO-BACK 70 FT APART. INSTALL FIRST DELINEATOR 75 FT NORTH OF AND ACROSS FROM POLE# 41/1/4415		7		
NB	MM 1.898, RT	A	VN-054	30	30			6.25							I		X							INSTALL NEW SIGN AND POST 120 FT SOUTH OF AND ACROSS FROM POLE# 4/3/13		8		
NB	MM 1.931, RT	A	VR-072 VR-072	24 24	30 30					X				X										RETAIN BACK-TO-BACK ENCORE SIGNS AND POST				
SB	MM 1.985, LT	F	TOWN SIGN	18	24																			REMOVE SIGN AND POST				
SB	MM 2.029, LT	F	WI-5	30	30								X		X									REMOVE SIGN AND POST				
		F	WI3-IP	18	18								X											REMOVE SIGN				
		F	WI-4	30	30			6.25							I		X							INSTALL NEW SIGN AND POST 280 FT NORTH OF AND ACROSS FROM POLE# 12	X			
NB	MM 2.394, RT	A	W3-1	36	36			9.00					X		X	2	X							INSTALL NEW SIGN ON 2-POSTS 137 FT SOUTH OF POLE# 413/2	X			
SB	MM 2.425, LT	F	VR-017	24	30			5.00					X		X	1	X							INSTALL NEW SIGN AND POST 26 FT NORTH OF AND ACROSS FROM POLE# 413/2	X			
		F	R2-1	24	30			5.00																INSTALL NEW SIGN BENEATH THE LEGAL LOAD LIMIT SIGN ON THE SAME POST	X			
SB	MM 2.455, LT	F	VR-017	24	30								X		X									REMOVE SIGN AND POST				
NB	MM 2.459, RT	A	RI-1	30	30					X				X										RETAIN EXISTING SIGN AND POST	X			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

SHEET SUBTOTALS

SF
35.50
41.75

EA 3 EA 9 EA 2 EA 6
EA 8 EA 2 EA 6
FT 48 FT 90 FT
LB LB LB LB

SF
EA 12-8
EA 8
EA 12
FT 138
EA
LB

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn PLOT DATE: 17-SEP-2012 11:33
PROJECT LEADER: JLS DRAWN BY: ITS
DESIGNED BY: NLA CHECKED BY: JLS
ST. ALBANS TRAFFIC SIGN SUMMARY SHEET 2 SHEET 42 OF 51