STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – WEYBRIDGE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS 8.00 "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.015, LT	E	OM3-L	12	36					X					X	1		X								RETAIN SIGN AND REPLACE POST			
NB	MM 0.015, RT	A	TOWN SIGN	30	36								X													REMOVE SIGN AND POST			
		A	OM3-R	12	30					X					X	1		X								RETAIN SIGN SLIDE UP TO CORRECT HEIGHT			
NB	MM 0.023, RT	A	VR-017	24	30			5.00								1		X								INSTALL NEW SIGN AND POST 40 FT SOUTH OF TYPE 3 OBJECT MARKER AT END OF BRIDGE, BEHIND GUARDRAIL		7	
NB	MM 0.104, RT	A	W5-3	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 16 FT NORTH OF POLE# 421/57/29-2	X		
NB	MM 1.582, RT	A	W5-3	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 174 FT NORTH OF AND ACROSS FROM POLE# 421/27	X		
		A	W16-3AP	30	12			2.50																		INSTALL BENEATH ONE LANE BRIDGE SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 1.610, RT	A	TOWN SIGN	24	30								X		X											REMOVE SIGN AND POST			
NB	MM 1.617, RT	A	TOWN SIGN	30	30								X		X											REMOVE SIGN AND POST			
		A	VR-493M	36	36			9.00								2		X								INSTALL NEW SIGN AND POST 11FT SOUTH OF AND ACROSS FROM POLE# 421/27		8	
		A	VR-017	24	30			5.00																		INSTALL NEW SIGN BENEATH RATTLIN BRIDGE REGULATORY SIGN ON LEFT POST AT THE CORRECT SIGN HEIGHT		7	
NB	MM 1.628, RT	A	W1-2R	30	30								X		X											REMOVE SIGN AND POST			
										EA 2	EA	EA	EA 4	EA	EA 5		FT	FT 135	FT		LB	LB	LB	LB					
							WEYBRIDGE SHEET TOTALS	SF 39.50	SF	EA ~~6~~				EA ~~5~~ 4		EA ~~9~~	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(5)

FILE NAME: 10k018_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WEYBRIDGE TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 17-SEP-2012 11:34
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 46 OF 51