STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - HARTFORD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	2.497 MM ~~2.523,~~ RT	A	WI-8 R	18	24		B-B	3.00								2		X								SEPARATE INSTALLED BACK-TO-BACK ON ~~A SIGN BRACKET AND A SINGLE~~ POSTS 180 ~~310~~ FT NORTH OF POLE* 8-50/25 ½	X		
		B	WI-8 L	18	24			3.00								+											X		
SB	2.517 MM ~~2.502,~~ LT	F	VW-060	30	30		HIDDEN DRIVES	6.25					X			2		X								272 INSTALL NEW SIGN AND POST ~~322~~ FT SOUTH OF THE INTERSECTION OF COSTELLO ROAD ON LEFT SIDE OLD RIVER ROAD, ~~200~~ FT SOUTH OF 150 GUARDRAIL END SECTION		8	
		F	WI-5 L	30	30			6.25					X													INSTALL NEW SIGN BENEATH THE HIDDEN DRIVES WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	2.510 MM ~~2.516,~~ RT	A	WI-IMb R	30	30			6.25								1		X								285 INSTALL NEW SIGN AND POST ~~248~~ FT SOUTH OF THE INTERSECTION OF COSTELLO ROAD ON THE RIGHT SIDE OF RIVER ROAD, ~~127~~ FT SOUTH AND 174 ACROSS FROM GUARDRAIL END SECTION		8	
		A	WI6-8P	30	8		Costello Rd	1.67																		INSTALL NEW SIGN BENEATH MODIFIED TURN RIGHT WARNING SIGN		8	
SB	MM 2.518, LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
		F	VW-060A	30	30		HIDDEN DRIVE						X													REMOVE SIGN			
SB	MM 2.542, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 121 FT SOUTH OF THE INTERSECTION OF COSTELLO ROAD ON LEFT SIDE OLD RIVER ROAD NEAR END CURL OF GUARDRAIL SECTION	X		
NB	MM 2.568, RT	C/D	D3-1	30	6		Costello Rd						X		X											REMOVE SIGN AND POST			
		A/B	D3-1	36	6		Old River Rd						X													REMOVE SIGN			
SB	MM 2.568, LT	E/F	D3-1	36	12		Costello Rd	3.00					X													INSTALL NEW ABOVE OLD RIVER ROAD SIGN ABOVE STOP SIGN		8	
		G/H	D3-1	42	12		Old River Rd	3.50					X													INSTALL NEW SIGN ABOVE STOP SIGN AND BENEATH COSTELLO RD SIGN ON SAME POST		8	
		F	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION	X		
NB	2.580 MM ~~2.572~~, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								110 ~~148~~ FT NORTH OF THE INTERSECTION OF COSTELLO ROAD ON RIGHT SIDE OF OLD RIVER ROAD BEHIND GUARDRAIL	X		
NB	MM 2.586, RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
										EA	EA	EA	EA 10 ~~6~~	EA	EA 4			FT 105			LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 49.17	SF				EA ~~6~~ 10		EA 4	EA 7		FT 105		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(6)

FILE NAME: 10k020_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HARTFORD TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-JUN-2010
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 13 OF 44