STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 - HARTFORD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							TOTAL TSS SHEET 11	55.57					8 ~~5~~		5	7	93.5	~~105~~										
							TOTAL TSS SHEET 12	81.91					3 ~~4~~		3	14	211.5	~~210~~										
							TOTAL TSS SHEET 13	49.17					10 ~~6~~		4	7	113.0	~~105~~										
							TOTAL TSS SHEET 14	91.25 ~~97.50~~					3		3	18	238.5	~~270~~										
							TOTAL TSS SHEET 15	41.5 ~~38.00~~					5 ~~3~~		3	7	86.0	~~105~~										
							HARTFORD SHEET TOTALS	SF 319.40 ~~322.15~~	SF	EA 21 (EA 21 / EA 21 / EA 21 / EA 29 ~~21~~)				EA 18 (EA 18 / EA 18)		EA 53	FT 742.50 ~~795~~ (FT 742.50 ~~795~~ / FT)			EA	LB (LB / LB / LB / LB)							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(6)

FILE NAME: 10k020_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
HARTFORD TRAFFIC SIGN SUMMARY 6

PLOT DATE: 04-JUN-2010
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 16 OF 44