STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - NEWFANE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							RIVER ROAD																						
SB	MM 0.017, LT	E	RI-1	30	30		STOP	6.25					X		X	I		X									REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION ON THE RIGHT SIDE OF THE ROAD WHEN TRAVELING SOUTH ON RIVER RD (RIVER RD AND RADWAY HILL RD INTERSECTION)	X		
NB	MM 0.025, RT	A	RI-1	30	30		STOP	6.25					X		X	I		X									REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION ON THE LEFT SIDE OF THE ROAD WHEN TRAVELING SOUTH ON RIVER RD (RIVER RD AND RADWAY HILL RD INTERSECTION)	X		
		C	D3-1	30	12		River Rd	2.50					X														INSTALL NEW SIGN ABOVE RADWAY HILL RD SIGN ON SAME POST		8	
		B	D3-1	48	12		Radway Hill Rd	4.00					X														INSTALL NEW SIGN ABOVE STOP SIGN AT SAME LOCATION ON THE SAME POST		8	
SB	MM 0.025, LT TO MM 0.0704, LT	F		6	8		(5) TYPE II - 6" X 8" WHITE DELINEATORS	1.67								5	X										INSTALL 5 SINGLE DELINEATORS 60 FT APART ON THE RIGHT SIDE OF RIVER RD GOING SOUTH. INSTALL THE FIRST ONE OPPOSITE THE LEFT HAND SIDE STOP SIGN		7	
NB	MM 0.025, RT TO MM 0.704, RT	A		6	8		(5) TYPE II - 6" X 8" WHITE DELINEATORS	1.67								5	X										INSTALL 5 SINGLE DELINEATORS 60 FT APART ON THE LEFT SIDE OF RIVER RD GOING SOUTH. INSTALL THE FIRST ONE AT THE LEFT HAND SIDE STOP SIGN		7	
SB	MM 0.035, LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								I		X									INSTALL NEW SIGN AND POST ABOUT ~~182~~ 150' FT FROM THE CENTER OF THE INTERSECTION		7	
		F	R2-1	24	30		SPEED LIMIT 30	5.00																			INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT SIGN ON THE SAME POST AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.082, LT	F	R2-1	24	30		SPEED LIMIT 30						X		X												REMOVE SPEED LIMIT SIGN AND POST			
NB	MM 0.085, RT	A	W3-1	36	36			9.00								2		X									INSTALL NEW SIGN AND POST ABOUT ~~445~~ 375' FT FROM THE CENTER OF THE INTERSECTION	X		
NB	MM 0.408, RT TO MM 0.479, RT	A B		6	8		(14) TYPE II - 6" X 8" WHITE DELINEATORS	4.67								7	X										INSTALL 7 DELINEATORS BACK-TO-BACK (14 TOTAL) 60 FT APART ON THE LEFT SIDE OF RIVER RD GOING SOUTH. INSTALL THE FIRST ONE ABOUT 42 FT SOUTH OF POLE #8/662/8		7	
NB	MM 0.519, RT TO MM 0.5416, RT	A B		6	8		~~(6)~~ 8 TYPE II - 6" X 8" WHITE DELINEATORS	~~2.00~~ 2.67								3	X										INSTALL ~~(3~~ DELINEATORS BACK-TO-BACK ~~(6~~ 8 TOTAL) 60 FT APART ON THE LEFT SIDE OF RIVER RD GOING SOUTH BETWEEN THE TWO SERIES OF GUARDRAIL. INSTALL THE FIRST ONE AT THE SOUTH END OF THE FIRST GUARDRAIL BEING ENCOUNTERED AFTER POLE #8/662/8 WHENT TRAVELING SOUTH		7	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

										EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB				
													5		3		160	75											
SHEET SUBTOTALS								SF ~~48.01~~ 48.68	SF	EA 5				EA 3		EA 25	FT 235			EA	LB								

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(6)

FILE NAME: 10k020_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
NEWFANE TRAFFIC SIGN SUMMARY 2

PLOT DATE: 04-JUN-2010
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 18 OF 44