STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - NORWICH 1 (TURNPIKE ROAD)

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.282, RT	A	R8-3	24	24			4.00 •4.00								1		X		•THIS SIGN WAS STOLEN BY VANDALS. IT WAS REPLACED ON 11-9-11 BY THE CONTRACTOR.						INSTALL NEW SIGN AND POST ~~389~~ 425 FT NORTH OF POLE# GMP/8/NET/8	X		
NB	MM 0.298, RT	A	TOWN SIGN	24	30								X		X											REMOVE SIGN AND POST			
NB	MM 0.310, RT	A	W1-10 R	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS ~~539 FT NORTH OF POLE# GMP/8/NET/8~~	X		
		A	W16-8P	24	8		MOORE LN TURNPIKE RD	1.33																		INSTALL NEW SIGN BENEATH HORIZONTAL ALIGNMENT WITH SIDE ROAD WARNING SIGN AT CORRECT SIGN HEIGHT		9	
SB	MM 0.359, LT	A	W-622	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 259 FT NORTH OF POLE# GMP/12/NET/12		9	
SB	MM 0.401, LT	H	R1-1	30	30			6.25			2	2	~~X~~ 3		X	1		X								REMOVE EXISTING SIGN AND POST INSTALL NEW SIGN AT SAME LOCATION	X		
NB	MM 0.404, RT	C	D4-2 R	30	36								X		X											REMOVE SIGN AND POST. RETURN TO TOWN			
NB	MM 0.406, RT	C	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS DIRECTLY ACROSS FROM MOORE LANE INTERSECTION. 190 FT SOUTH OF AND ACROSS FROM POLE# 70/1/GMP/72488/17	X		
SB	MM 0.444, LT	F	W1-2Mf L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 539 FT NORTH OF POLE# GMP/8/NET/8	X		
		F	W16-8P	24	8			1.33																		INSTALL NEW SIGN BENEATH HORIZONTAL ALIGNMENT WITH SIDE ROAD RIGHT WARNING SIGN AT CORRECT SIGN HEIGHT		9	
NB	MM 0.505, RT	A	R2-1	24	30			5.00					X		X	1		X								INSTALL NEW SIGN AND POST DIRECTLY ACROSS FROM POLE# 109705/20/GMP/4	X		
SB	MM 0.506, LT	F	R2-1	24	30			5.00					~~X~~		~~X~~	1		X								INSTALL NEW SIGN AND POST 10 ~~5~~ FT NORTH OF POLE# 109705/20/GMP/4	X		
SB	MM 0.532, LT	F	R2-1	24	30		25						X		X											REMOVE SIGN AND POST	X		
							SHEET SUBTOTALS	SF ~~52.81~~ 56.81	SF	EA 6				EA 6		EA 10		FT 150		EA		LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME:	STATEWIDE SOUTHEAST REGION		
PROJECT NUMBER:	STP HRRR(6)		
FILE NAME:	10k020_wrk.dgn	PLOT DATE:	04-JUN-2010
PROJECT LEADER:	JLS	DRAWN BY:	ITS
DESIGNED BY:	NLA	CHECKED BY:	JLS
NORWICH 1 TRAFFIC SIGN SUMMARY 2		SHEET 22	OF 44