

TRAFFIC SIGN SUMMARY SHEET 1 - TOWNSHEND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (In)			TUBULAR STEEL (In)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL																									
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER																						
																														lb/ft	lb/ft	lb/ft	lb/ft																		
SB	MM 0.274, LT	F	M2-1	21	15			2.19						X	X	2		X					X	INSTALL NEW SIGN AND POST 269 FT NORTH OF THE CENTER OF PEAKED MOUNTAIN RD			E-136B																								
		F	MI-5	24	24			4.00																INSTALL NEW SIGN BENEATH JCT SIGN ON THE SAME POSTS			E-136B																								
		F	M4-6	24	12			2.00																INSTALL NEW SIGN AND POST 269 FT NORTH OF THE CENTER OF PEAKED MOUNTAIN RD ADJACENT TO JCT 30 SIGN ASSEMBLY			E-136B																								
		F	M3-3	24	12			2.00																INSTALL NEW SIGN BENEATH END SIGN ON SAME POST	X																										
		F	MI-5A	24	24			4.00																INSTALL NEW SIGN BENEATH SOUTH SIGN ON SAME POST	X																										
		F	VD-700	6	10						X	X	X											REMOVE AND SALVAGE EXISTING SIGN AND INSTALL ON NEW ROUTE MARKER SIGN ASSEMBLY'S NEW POST																											
NB	MM 0.278, RT	A	R2-1	24	30			5.00						X	X	1		X						INSTALL NEW SIGN AND POST AT SAME LOCATION 290 FT NORTH OF THE CENTER OF PEAKED MOUNTAIN RD	X																										
SB	MM 0.289, LT	F	R2-1	24	30																			REMOVE SIGN AND POST																											
SB	MM 0.388 ^{0.398} , LT	F	R2-1	24	30			5.00																INSTALL NEW SIGN AND POST ^{32' NORTH} 15-SOUTH OF POLE # 12/3/783	X																										
NB	MM 0.444, RT	A	W11-2	30	30	F-Y-G		6.25																INSTALL NEW SIGN AND POST ^{40' NORTH} ACROSS- FROM DRIVE # 409	X																										
		A	W16-9P	24	12	F-Y-G		2.00																INSTALL NEW SIGN BELOW NEW PEDESTRIAN SIGN	X																										
SB	MM 0.512, LT	F	R2-1	24	30																			REMOVE SIGN AND POST																											
										EA	EA	EA	EA	EA	EA		FT	FT	FT	LB	LB	LB	LB																												
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".										EA				FT			LB																																		
SHEET SUBTOTALS								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	EA	LB																														
								32.44		9	4	5	75	75																																					
																						PROJECT NAME: STATEWIDE SOUTHEAST REGION			PROJECT NUMBER: STP HRRR(6)			FILE NAME: I0K020_wrk.dgn			PLOT DATE: 04-JUN-2010			PROJECT LEADER: JLS			DRAWN BY: ITS			DESIGNED BY: NLA			CHECKED BY: JLS			TOWNSHEND TRAFFIC SIGN SUMMARY I			SHEET 29 OF 44		