STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 - TOWNSHEND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 3.425, LT	F	M3-3	24	12		SOUTH	2.00								1		X								INSTALL ABOVE THE M1-5A SIGN (333 FT SOUTH OF THE CENTER OF GRAFTON ROAD).	X		
		F	M1-5A	24	24		35	4.00																		INSTALL SIGN AND POST (333 FT SOUTH OF THE CENTER OF GRAFTON ROAD)	X		
NB	MM 3.451, RT	A	R2-1	24	30		SPEED LIMIT 50						X		X											REMOVE SIGN AND POST	X		
SB	MM 3.451, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 195 FT SOUTH OF THE CENTER OF GRAFTON RD ACROSS FROM THE 50 MPH SPEED LIMIT SIGN	X		
SB	MM 3.454, LT	F	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN AND POSTS (180 FT SOUTH OF THE CENTER OF GRAFTON RD)			
SB	MM 3.511, LT	E	TOWN SIGN	24	6		← GRAFTON						X		X											REMOVE SIGN AND POST			
		E	M3-1	24	12		NORTH						X													REMOVE SIGN	X		
		E	M1-5A	24	24		35						X													REMOVE SIGN	X		
		E	M6-3	21	15		↗						X													REMOVE SIGN	X		
NB	MM 3.518, RT	A	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST (85 FT NORTH OF POLE #5-115/5/115/3/683)	X		
SB	MM 3.534, LT	F	W3-5	36	36		↑ SPEED LIMIT 40	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS (237 FT NORTH OF POLE #5-115/5/115/3/683)	X		
NB	MM 3.556, ~~L~~ R T	A	M3-1	24	12		NORTH	2.00					X			1		X								INSTALL NEW SIGN AND POST ~~234~~ 180 FT NORTH OF POLE# 5-115/5/115/3/683	X		
		A	M1-5A	24	24		35	4.00					X													INSTALL NEW SIGN BENETAH NORTH CARDINAL DIRECTIONAL SIGN ON THE SAME POST	X		
SB	MM 3.577, LT	F	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
							SHEET SUBTOTALS	SF 31.00	SF	EA 9				EA 4		EA 6	FT 90			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(6)

FILE NAME: 10k020_wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
TOWNSHEND TRAFFIC SIGN SUMMARY 5

PLOT DATE: 04-JUN-2010
DRAWN BY: ITS
CHECKED BY: JLS
SHEET 33 OF 44