STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 - TOWNSHEND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 3.594, RT	A	D2-1	72	12		Athens 6	6.00								2		X								INSTALL NEW SIGN AND POST 382 FT NORTH OF POLE #5-115/5/115/3/683		10	
		A	D2-1	72	12		Cambridgeport 8	6.00																		INSTALL NEW SIGN BENEATH ATHENS 6 DESTINATION SIGN ON THE SAME POSTS		10	
							GRAFTON RD																					
EB	MM 0.015, RT	A	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
WB	MM 0.037, LT	F	D2-1	72	12		Grafton 6	6.00								2		X								INSTALL NEW SIGN ON 2-POSTS 200 FT WEST FROM THE BEGNINNING OF GRAFTON RD		10	
EB	MM 0.0975 ~~0.0758~~, RT	A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2- POSTS 515 ~~400~~ FT WEST FROM THE BEGINING OF GRAFTON RD	X		
EB	MM 0.200, RT	A	W3-1	30	30								X		X											REMOVE SIGN AND POST (1056 FT WEST FROM THE BEGINNING OF GRAFTON RD)			
WB	MM 0.718, LT TO MM 0.974, LT	F E		6	8		50 ~~(32)~~ TYPE II - 6" X 8" WHITE DELINEATORS	16.67 ~~10.67~~								25 ~~16~~	X									INSTALL DELINEATORS BACK-TO-BACK 85 FT APART. INSTALL FIRST DELINEATOR AT MILE POINT 0.718. INSTALL LAST DELINEATOR AT MILE POINT ~~0.974.~~ MEET ON SITE WITH ROAD FOREMAN KURT BOSTROM (365-4260) TO CONFIRM LOCATION 1.118		7	
							EAST HILL RD																					
EB	MM 0.020, RT	A	OM3-R	12	36								~~X~~ MISSING		~~X~~											REMOVE SIGN AND POST			
EB	MM 0.028, RT	A	OM3-R	12	36			3.00								1		X								INSTALL NEW OBJECT MARKER AND POST ON THE RIGHT SIDE OF THE WEST END OF THE BRIDGE	X		
WB	MM 0.028, LT	E	OM3-L	12	36			3.00								1		X								INSTALL NEW OBJECT MARKER AND POST ON THE LEFT SIDE OF THE WEST END OF THE BRIDGE	X		
EB	MM 0.038, RT	B	OM3-R	12	36			3.00								1		X								INSTALL NEW OBJECT MARKER AND POST ON THE RIGHT SIDE OF THE EAST END OF THE BRIDGE WITH SIGN FACING EAST	X		
WB	MM 0.038, LT	F	OM3-L	12	36			3.00								1		X								INSTALL NEW OBJECT MARKER AND POST ON THE LEFT SIDE OF THE EAST END OF THE BRIDGE WITH SIGN FACING EAST	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60
			EA	EA	EA	EA ~~2~~ 3	EA	EA		FT 128	FT 165	FT		LB	LB	LB	LB
SHEET SUBTOTALS	SF ~~55.92~~ 61.92	SF	EA 3				EA 3		EA 27	FT 293			EA	LB			

PROJECT NAME:	STATEWIDE SOUTHEAST REGION
PROJECT NUMBER:	STP HRRR(6)
FILE NAME:	10k020_wrk.dgn
PROJECT LEADER:	JLS
DESIGNED BY:	NLA
TOWNSHEND TRAFFIC SIGN SUMMARY 6	
PLOT DATE:	04-JUN-2010
DRAWN BY:	ITS
CHECKED BY:	JLS
SHEET	34 OF 44