

# TRAFFIC SIGN SUMMARY SHEET 1 - WINDSOR

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXISTING POST		NO. OF NEW POSTS	SQUARE STEEL (In)			TUBULAR STEEL (In)				SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL							
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		FOUNDAION			lb/ft						DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER					
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00										
WB	MM 0.377, LT	F	W11-2	30	30	F-Y-G		6.25								1	X							INSTALL NEW SIGN AND POST JUST BEFORE FITCH STREET COURT	X								
		F	W16-7P	24	12	F-Y-G		2.00																INSTALL BENEATH THE PEDESTRIAN SIGN, POINTING TOWARDS THE ROAD	X								
EB	MM 0.391, RT	A	R2-1	24	30							X	X											REMOVE SIGNS AND POST AND INSTALL A NEW PEDESTRIAN SIGN ON A NEW POST									
		A	W11-2	30	30	F-Y-G	MUSEUM RD	6.25		X	X	X	X		1	X								REMOVE SIGNS AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION	X								
		A	W16-7P	24	12	F-Y-G		2.00																INSTALL BENEATH THE PEDESTRIAN SIGN, POINTING TOWARDS THE ROAD	X								
EB	MM 0.441, RT	A	R2-1	24	30			5.00							1	X								INSTALL NEW SIGN AND POST 260 FT WEST OF THE CENTER OF FITCH ST	X								
WB	MM 0.444, LT	F	W1-10L	36	36			9.00							2	X								INSTALL NEW SIGN AND POSTS 260 FT WEST OF THE CENTER OF FITCH ST	X								
		F	W16-8P	30	8		Ascutney St	1.67																INSTALL BENEATH THE CURVE/INTERSECTION WARNING SIGN		9							
WB	MM 0.463, LT	H	RI-1	30	30			6.25				X	X		1	X								REMOVE SIGN AND POST AND INSTALL NEW SIGN AND POST AT THE SAME LOCATION	X								
WB	MM 0.464, LT	K	D9-2	24	24		0440 1423 0453	4.00		X	X	X	X		1	X								INSTALL NEW SIGN AND POST IN THE ISLAND NEXT TO POLE # 19, FACING UNION ST	X								
		K	M6-2	21	15			2.19				X												INSTALL NEW SIGN BENEATH HOSPITAL SYMBOL SIGN ON SAME POST	X								
WB	MM 0.467, LT	K	M3-4	24	12			2.00				X	X		1	X								INSTALL NEW SIGNS AND POST IN THE ISLAND NEXT TO POLE 18A, FACING UNION ST TO THE RIGHT OF THE HOSPITAL SYMBOL SIGN ASSEMBLY				E-136B					
		K	M1-6	24	24			4.00				X												INSTALL NEW SIGN BENEATH WEST CARDINAL DIRECTIONAL SIGN ON SAME POST				E-136B					
		K	M6-2	21	15			2.19				X												INSTALL NEW SIGN BENEATH VT 44 ROUTE MARKER ON THE SAME POST				E-136B					
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".																																	
<b>SHEET SUBTOTALS</b>								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								52.80		8	5	8																					

PROJECT NAME: STATEWIDE SOUTHEAST REGION  
 PROJECT NUMBER: STP HRRR(6)  
 FILE NAME: I0K020\_wrk.dgn  
 PROJECT LEADER: JLS  
 DESIGNED BY: NLA  
 WINDSOR TRAFFIC SIGN SUMMARY I

PLOT DATE: 04-JUN-2010  
 DRAWN BY: ITS  
 CHECKED BY: JLS  
 SHEET 36 OF 44