STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - WINDSOR

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
WB	MM 0.526, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		X								INSTALL NEW SIGN AND POST ~~42~~ 92 FT WEST OF THE CENTER OF CEMETERY ROAD ~~NEXT TO BUT NOT BLOCKING PEDESTRIAN WARNING SIGN ASSEMBLY~~	X		
EB	MM 0.527, RT	A	W11-2	30	30	F-Y-G		6.25					X		X	1		X								INSTALL NEW PEDESTRIAN SIGN AND POST AT THE SAME LOCATION FOR CROSSWALK AT CEMETERY ROAD	X		
		A	R2-1	24	30		SPEED LIMIT 25						X													REMOVE SIGN			
		A	W16-7P	24	12	F-Y-G		2.00																		INSTALL NEW SIGN BENEATH THE PEDESTRIAN SIGN ON THE SAME POST	X		
EB	MM 0.558, RT	A	VR-615	36	36		LEFT TURN YIELD TO THRU TRAFFIC						X		X											REMOVE SIGN AND POST			
		A	W1-2MnR	30	30			6.25								1		X								INSTALL A NEW CURVE/INTERSECTION WARNING SIGN AND ~~10~~ 20 FT EAST OF POLE# 13/16/NET		9	
		A	W16-8P	30	8		Ascutney St	1.67																		INSTALL NEW SIGN BENEATH THE CURVE/INTERSECTION WARNING SIGN		9	
EB	MM 0.581, RT	A	M3-2	24	12		EAST	2.00								1		X								INSTALL NEW SIGN AND POST ~~16~~ 20 FT EAST OF POLE # 14/NET/17			E-136B
		A	M1-6	24	24		VERMONT 44	4.00																		INSTALL NEW SIGN BENEATH EAST CARDINAL DIRECTIONAL SIGN ON THE SAME POST			E-136B
		A	M5-2R	21	15			2.19																		INSTALL NEW SIGN BENEATH VT 44 ROUTE MARKER ON THE SAME POST			E-136B
EB	MM 0.608, RT	A	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 11FT WEST OF POLE# 15/18713/18	X		
							SHEET SUBTOTALS	SF 34.36	SF	EA 4				EA 3		EA 5	FT 75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME:	STATEWIDE SOUTHEAST REGION
PROJECT NUMBER:	STP HRRR(6)
FILE NAME: 10k020_wrk.dgn	PLOT DATE: 04-JUN-2010
PROJECT LEADER: JLS	DRAWN BY: ITS
DESIGNED BY: NLA	CHECKED BY: JLS
WINDSOR TRAFFIC SIGN SUMMARY 3	SHEET 38 OF 44