STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - ARLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.010, LT	F	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.013, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION ACROSS FROM STOP SIGN ASSEMBLY		7	
NB	MM 0.013, RT	A	VR-017	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN BENEATH NEWLY INSTALLED LEGAL LOAD LIMIT SIGN AT THE APPROPRIATE SIGN HEIGHT	X		
NB	MM 0.033, RT	A	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE SIGN AND POST			
NB	MM 0.068, RT	A	WI-5R	30	30			6.25								1		X								INSTALL NEW SIGN AND PLAQUE 32 FT SOUTH OF TWENTY ACRE WOOD (PVT) ROAD	X		
		A	W7-3a	24	18		NEXT 1 MILE	3.00																		INSTALL BENEATH WINDING ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.087, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN 95 FT NORTH OF AND ACROSS FROM MAILBOX #1799	X		
NB	MM 0.113, RT TO MM 0.132, RT	A/B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS	2.67								4	X									INSTALLED BACK-TO-BACK AT 25 FT± SPACING BEGINING 79 FT± NORTH OF POLE #3/6/202		7	
SB	MM 0.176, LT	F	WI-6L	48	24			8.00								2		X								INSTALL NEW SIGN 190 FT± NORTH OF AND ACROSS FROM POLE #4	X		
SB	MM 0.183, LT TO MM 0.202, LT	F/E		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS	3.33								5	X									INSTALLED BACK-TO-BACK AT 25 FT± SPACING BEGINING 63 FT± SOUTH OF POLE #10-1-2/5/6/204		7	
NB	MM 0.180, RT	A	OM-3R	12	36			3.00								1		X								INSTALL AT THE POINT IN WHICH THE GUARDRAIL BENDS OUT CLOSEST TO THE ROADWAY	X		
NB	MM 0.826, RT	A	W2-2L	30	30			6.25								1		X								INSTALL SIGN AND PLAQUE 127 FT SOUTH OF END OF GUARDRAIL	X		
		A	WI6-8P	24	8		Farm Road	1.33																		INSTALL BENEATH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
							SHEET SUBTOTALS	SF 59.08	SF	EA 3			EA 3	EA 3		EA 19	FT 72	FT 150	FT 222	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
ARLINGTON TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 14 OF 78