STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - BRIDPORT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.195, LT	F	WI-IMaL	30	30			6.25								I		X								INSTALL NEW SIGN AND POST 174 FT NORTH OF POLE #4/1/9II-1 NEAR POLE # 38I/4/2		8	
		F	WI3-IP	I8	I8			2.25																		INSTALL NEW SIGN BENEATH NEWLY INSTALLED MODIFIEDTURN WARNING SIGN AT THE APPROPRIATE SIGN HEIGHT	X		
SB	MM 0.245, LT	H	RI-1	30	30			6.25								I		X								INSTALL NEW SIGN AND POST 30 FT WEST OF THE INTERSECTION LOVER'S LANE SLIP RAMP & CROWN POINT RD FOR EASTBOUND TRAFFIC	X		
SB	MM 0.264, LT	H	RI-1	30	30			6.25					X		X	I		X								INSTALL NEW SIGN AND POST 47 FT WEST OF THE INTERSECTION OF LOVER'S LANE & CROWN POINT ROAD FOR EASTBOUND TRAFFIC	X		
SB	MM 0.269, LT	F	TOWN SIGN	I2	I8								X		X											REMOVE SIGN AND POST			
		F	RI2-1	24	30			5.00								I		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN, 42 FT NORTH OF AND ACROSS FROM POLE #4/15T/9I-5	X		
		F	R2-1	24	30			5.00																		INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.317, RT	A	WI-IMbR	30	30			6.25								I		X								INSTALL NEW SIGN, PLAQUE AND POST 32 FT NORTH OF POLE #38I/6/CTC		8	
		A	WI3-IP	I8	I8			2.25																		INSTALL BENEATH MODIFIED TURN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.348, LT	F	SI-1	36	36	F-Y-G		9.00					X		X	2		X								INSTALL NEW SIGN AND POST I6 FT SOUTH OF AND ACROSS FROM POLE #7/CTC/2	X		
		F	WI6-9P	24	I2	F-Y-G		2.00																		INSTALL BENEATH SCHOOL SYMBOL WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.386, RT	A	TOWN SIGN	I2	I8								X		X											REMOVE SIGN AND POST			
SB	MM 0.4II, LT	H	RI-1	30	30			6.25					X		X	I		X								INSTALL NEW SIGN AND POST AT SOME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 0.487, RT	F	SI-1	36	36	F-Y-G		9.00					X		X	2		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN, 375 FT SOUTH OF CENTER OF SCHOOL DRIVE	X		
		F	WI6-9P	24	I2	F-Y-G		2.00																		INSTALL BENEATH SCHOOL SYMBOL WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
										EA 6	EA	EA	EA	EA	EA 6		FT 150				LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 67.75	SF	EA 6				EA 6		EA I0	FT I50			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: I0K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
BRIDPORT TRAFFIC SIGN SUMMARY I

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET I7 OF 78