STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - BRIDPORT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.547, LT	F	R12-1	24	30		WEIGHT LIMIT 10 TONS	5.00					X		X	1		X								INSTALL NEW SIGN ADF POST JUST BEHIND END OF BRIDGE RAIL	X		
NB	MM 0.573, RT	A	R12-1	24	30		WEIGHT LIMIT 10 TONS	5.00					X		X	1		X								INSTALL NEW SIGN AND POST JUST BEHIND END OF BRIDGE RAIL	X		
SB	MM 0.604, LT	F	TOWN SIGN	12	18		WATCH FOR CHILDREN						X		X											REMOVE SIGN AND POST			
NB	MM 0.663, RT	A	TOWN SIGN	12	18		~~SLOW CHILDREN~~ ON UTILITY POLE						~~X~~		X											REMOVE SIGN AND POST			
NB	MM 0.792, RT	A	TOWN SIGN	12	18		SLOW CHILDREN AT PLAY						X		X											REMOVE SIGN AND POST			
NB	MM 0.814, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN, 10 FT SOUTH OF POLE #13	X		
SB	MM 0.830, LT	F	R2-1	24	30		SPEED LIMIT 50	5.00																		INSTALL NEW SIGN AND POST 10 FT SOUTH OF AND ACROSS FROM POLE # 13 AND THE SPEED LIMIT 35 SIGN ASSEMBLY	X		
NB	MM 0.885, RT	A	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
		A	W3-5	36	36		SPEED LIMIT 35	9.00								2		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN, 10 FT SOUTH OF AND ACROSS FROM POLE #CTC/9/15	X		
SB	MM 0.950, LT	F	TOWN SIGN	12	18		~~SLOW CHILDREN AT PLAY~~ NOT IN FIELD						~~X~~		X											REMOVE SIGN AND POST			
NB	MM 0.936, RT	A	TOWN SIGN	12	18		NO THRU TRUCKS						X		X											REMOVE SIGN AND POST			
		A	R12-1	24	30		WEIGHT LIMIT 10 TONS	5.00								1		X								INSTALL NEW SIGN ON 2-POSTS AT SAME LOCATION AS REMOVED SIGN, 442 FT SOUTH OF POLE #CTC/9/15	X		
		A	R2-1	24	30		THIS IS A 50 MPH ZONE. SPEED LIMIT 35 THIS SIGN WAS NOT INSTALLED AND GIVEN TO TOWN.	5.00																		INSTALL BENEATH LEGAL LOAD LIMIT SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.971, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST AT SOME LOCATION AS REMOVED SIGN ASSEMBLY	X		
SB	MM 0.977, LT	G	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 5 FT SOUTH OF POLE #22 DIRECTLY ACROSS FROM THE INTESECTION OF SHORT STREET	X		
										EA	EA	EA	EA 10	EA	EA 10		FT	FT 135	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 53.25	SF	EA 10				EA 10		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
BRIDPORT TRAFFIC SIGN SUMMARY 2

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 18 OF 78