STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - BRIDPORT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.992, RT	A	TOWN SIGN	18	24		TRUCK ROUTE						X		X											REMOVE SIGN AND POST			
NB	MM 1.011, LT	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST 10 FT IN FRONT OF POLE # 381/23	X		
SB	MM 1.044, LT	F	W2-2	30	30			6.25								1		X								INSTALL NEW SIGN, PLAQUE AND POST 74 FT NORTH OF AND ACROSS FROM POLE #381/24	X		
		F	W16-8P	30	8		Swinton Rd	1.67																		INSTALL PLAQUE BENEATH SIDE ROAD WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
NB	MM 1.081, RT	A	TOWN SIGN	12	18		WATCH FOR CHILDREN						X		X											REMOVE SIGN AND POST			
		A	R2-1	24	30		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN, 121 FT SOUTH OF POLE #381/24	X		
NB	MM 1.107, RT	C	W1-7	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 21 FT NORTH OF POLE #4/3 DIRECTLY ACROSS FROM THE INTESECTION OF SWINTON ROAD	X		
SB	MM 1.111, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST AT SOME LOCATION AS REMOVED SIGN ASSEMBLY	X		
SB	MM 1.133, LT	F	R2-1	24	30		SPEED LIMIT 50 NOT IN FIELD	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 116 FT SOUTH OF AND ACROSS FROM POLE # 4/3	X		
SB	MM 1.165, LT	F	W1-2	30	30			6.25								1		X								INSTALL NEW SIGN AND POST DIRECTLY ACROSS FROM POLE #6	X		
		F	W13-1P	18	18		40 M.P.H.	5.00																		INSTALL BENEATH CURVE WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 1.241, RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALL NEW SIGNS BACK-TO-BACK ON ~~CHEVRON BRACK ON SAME POST~~ 401 FT SOUTH OF POLE #6	X X		
NB	MM 1.259, RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALL NEW SIGNS BACK-TO-BACK ON ~~CHEVRON BRACK ON SAME POST~~ 20 FT NORTH OF POLE #28	X X		
NB	MM 1.277, RT	A B	W1-8R W1-8L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALL NEW SIGNS BACK-TO-BACK ON ~~CHEVRON BRACK ON SAME POST~~ 75 FT SOUTH OF POLE # 28	X X		
							SHEET SUBTOTALS	SF 66.42	SF	EA 4			EA 4		EA 4	EA 11		FT 165		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
BRIDPORT TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 19 OF 78