STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - CASTLETON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 3.259, LT	F	W11A-2	30	30	F-Y-G							X		X											REMOVE EXISTING SIGN AND POST			
		F	W16-7P	24	12	F-Y-G							X													REMOVE PLAQUE			
		F	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST AT PREVIOUSLY REMOVED SIGN ASSEMBLY LOCATION, 16 FT WEST OF AND ACROSS FROM POLE#4/116/5	X		
		F	W16-7P	24	12	F-Y-G		2.00																		INSTALL BENEATH PEDESTRIAN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
EB	MM 3.295, RT	A	R2-1	24	30			5.00								1		X								INSTALL NEW SIGN AND POST AT A POINT 58 FT WEST OF POLE #4/113/88½	X		
WB	MM 3.296, LT	F	R2-1	24	30								X		X											REMOVE EXISTING SIGN AND POST			
		F	D1-1	72	20	"SPARTAN STADIUM"		10.00								2		X								INSTALL NEW SIGN ON 2- POST AT PREVIOUSLYREMOVED SIGN ASSEMBLY LOCATION, 85 FT EAST OF MARBLE MONUMENT		8	
EB	MM 3.347, RT	D	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
WB	MM 3.352, LT	A	W2-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS AT A POINT 69 FT EAST OF AND ACROSS FROM POLE #50T/4/119/165T/186	X		
		A	W16-8a	48	15			5.00																		INSTALL BENEATH INTERSECTION WARNING SIGN AT THE CORRECT SIGN HEIGHT		8	
							NORTH ROAD																						
SB	MM 0.011, LT	F	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.022, RT	A	VR-017	24	30			5.00								1		X								INSTALL NEW SIGN AND POST AT PREVIOUSLY REMOVED SIGN ASSEMBLY LOCATION. INSTALL 58 FT SOUTH OF POLE #165T/L402/P2/3		7	
		A	R2-1	24	30			5.00					X		X											REMOVE SIGN AND POST INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT SIGN AT SAME LOCATION AT CORRECT SIGN HEIGHT	X		
		A	W11-2	30	30								X													REMOVE SIGN			
							SHEET SUBTOTALS	SF 59.75	SF	EA 7				EA 5		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME:	STATEWIDE SOUTHWEST REGION		
PROJECT NUMBER:	STP HRRR(7)		
FILE NAME: 10K022.DGN		PLOT DATE:	04-MAY-2010
PROJECT LEADER: N. AVERY		DRAWN BY:	N.AVERY
DESIGNED BY:	N. AVERY	CHECKED BY:	J. SCHULTZ
CASTLETON TRAFFIC SIGN SUMMARY 2		SHEET	24 OF 78