STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - CASTLETON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							NORTH ROAD (CONTINUED)																						
NB	MM 0.049, RT	A	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 63 FT SOUTH OF POLE #402/3/165B/2	X		
		A	W16-9P	24	12	F-Y-G		2.00																		INSTALL BENEATH PEDESTRIAN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.067, LT	F	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 32 FT NORTH OF POLE AND ACROSS FROM POLE #402/3/165B/2	X		
NB	MM 0.115, RT	A	W10-1	36	36			7.07								1		X								INSTALL NEW SIGN AND POST 69 FT SOUTH OF POLE #165/452/4J/5	X		
SB	MM 0.153, LT	A	W10-1	36	36			7.07								1		X								INSTALL NEW SIGN AND POST 63 FT NORTH OF POLE #30T/6/1	X		
SB	MM 0.193, LT	F	W10-1	36	36								X		X											REMOVE SIGN AND POST			
		F	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS PREVIOUSLY REMOVED SIGN ASSEMBLY, 275 FT NORTH OF POLE #30T/6/1	X		
		F	W16-9P	24	12	F-Y-G		2.00																		INSTALL BENEATH PEDESTRIAN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
							SOUTH STREET																						
NB	MM 0.011, RT	A	R1-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 0.030, LT	F	VR-079	24	30			5.00								1		X								INSTALL NEW SIGN AND POST 10 FT ACROSS FROM AND NORTH OF POLE #165B/7/P2. INSTALL SPEED LIMIT 30 BELOW THIS SIGN.		8	
		F	R2-1	30	30			5.00					X		X											REMOVE SIGN AND POST. INSTALL NEW SIGN BENEATH LEGAL LOAD LIMIT SIGN AT SAME LOCATION, AT CORRECT SIGN HEIGHT	X		
										EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
													3		3			120											
							SHEET SUBTOTALS	SF 55.89	SF	EA 3				EA 3		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
CASTLETON TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 25 OF 78