STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.016, RT	A	RI-1	36	36		STOP	9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS AT SOME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 0.016, LT	B	RI-1	36	36		STOP	9.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS AT SOME LOCATION AS REMOVED SIGN ASSEMBLY	X		
SB	MM 0.025, LT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS NOT IN FIELD						X		X											REMOVE SIGN AND POST			
SB	MM 0.045, LT	F	R3-4	24	24								X		X											REMOVE SIGN AND POST			
		F	TOWN SIGN	18	12		NO U TURN						X													REMOVE SIGN			
		F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								INSTALL NEW SIGN AND POST 887 FT NORTH OF AND ACROSS FROM POLE# 136/3 DO NOT BLOCK STOP SIGN		7	
NB	MM 1.107, RT	A	VR-925	36	30		ONLY ONLY	7.50								1		X								INSTALL NEW SIGN ON 2-POSTS 454 FT NORTH POLE# 136/3			E-145A
SB	MM 1.107, LT	F	VR-925	36	30		ONLY ONLY	7.50								1		X								INSTALL NEW SIGN ON 2-POSTS 454 FT NORTH OF AND ACROSS FROM POLE# 136/3 ACROSS FROM MATCHING SIGN			E-145A
NB	MM 0.143, RT	A	TOWN SIGN	48	48		STOP AT FOOT OF HILL						X		X X											REMOVE SIGN AND POSTS			
		A	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 264 FT NORTH POLE# 136/3	X		
SB	MM 0.143, LT	E	W3-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 264 FT NORTH OF AND ACROSS FROM POLE# 136/3 ACROSS FROM MATCHING SIGN	X		
NB	MM 0.205, RT	A	W3-1	48	48		STOP AHEAD						X		X X											REMOVE SIGN AND POSTS			
		A	W7-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 63 FT SOUTH POLE# 136/3	X		
SB	MM 0.205, LT	E	W7-1	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 63 FT SOUTH OF AND ACROSS FROM POLE# 136/3 ACROSS FROM MATCHING SIGN	X		
							SHEET SUBTOTALS	SF 74.00	SF	EA 7				EA 8		EA 15	FT 225			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 28 OF 78