STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 – KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft	SQUARE STEEL (In) 2.00 lb/ft	SQUARE STEEL (In) 2.50 lb/ft	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft	TUBULAR STEEL O/(In) 3.50 lb/ft	TUBULAR STEEL O/(In) 4.00 lb/ft	TUBULAR STEEL O/(In) 5.00 lb/ft	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
SB	MM 0.205, LT	F	R2-1	30	36		SPEED LIMIT 35	7.50					X		X	1		X								INSTALL NEW SIGN AND POST 63 FT SOUTH OF AND ACROSS FROM POLE# 136/3 IN FRONT OF HILL SYMBOL	X		
		F	TOWN SIGN	24	12		RADAR ENFORCED						X													REMOVE SIGN			
SB	MM 0.230, LT	E/F	D3-1	36	6		Anthony Way						X		X											REMOVE SIGN		9	
SB	MM 0.240, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
		E/F	D3-1	42	12		Anthony Way	3.50																		INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9	
SB	MM 0.273, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 74 FT NORTH OF AND ACROSS FROM POLE# 3/138	X		
		F	R4-1	24	30		DO NOT PASS						X													REMOVE SIGN			
NB	MM 0.625, RT	A	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 1088 FT SOUTH OF AND ACROSS FROM EXISTING SPEED RADAR FEEDBACK SIGN	X		
		A	R4-2	24	30		PASS WITH CARE						X													REMOVE SIGN			
SB	MM 0.673, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 1341 FT SOUTH OFTHE EXISTING SPEED RADAR FEEDBACK SIGN	X		
		F	TOWN SIGN	24	12		RADAR ENFORCED						X													REMOVE SIGN			
NB	MM 0.723, RT	D	R1-1	30	30		STOP	6.25					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
		A/B	D3-1	30	12		Merrill Dr	2.50																		INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9	
NB	MM 0.733, RT	A/B	D3-1	24	30		Merrill Dr						X		X											REMOVE SIGN AND POST			
NB	MM 0.783, RT	A	R2-1	00	00		SPEED LIMIT 35	5.00					X		X	1		X									X		
										EA	EA	EA	EA 13	EA	EA 9		FT	FT 105	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 46.00	SF	EA 13				EA 9		EA 7	FT 84			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 2

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 29 OF 78