STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 – KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.008, RT	C/D	D3-1	42	12		West Hill Rd	3.50					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY		9	
		A/B	D3-1	42	12		Killington Rd	3.50					X													INSTALL NEW SIGN BELOW WEST HILL RD STREET NAME SIGN IN THE SAME SIGN ASSEMBLY		9	
NB	MM 1.013, RT	D	TOWN SIGN	30	36		STOP HERE ON RED TO ACTIVATE SIGNAL						X		X											REMOVE SIGN AND POST INSTALL NEW SIGN AT THE SAME LOCATION			
		D	R10-6	24	36		STOP HERE ON RED	6.00								1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 1.026, RT	B A	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								2 ~~1~~		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 174 FT SOUTH OF THE SIGNALIZED WEST HILL RD INTERSECTION	X X		
SB	MM 1.046, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALLED BACK-TO-BACK ON A SIGN BRACKET ON A SINGLE POST 148 FT SOUTH OF AND ACROSS FROM THE SIGNALIZED WEST HILL RD	X		
		F	R4-1	24	30		DO NOT PASS						X													REMOVE SIGN			
NB	MM 1.051, RT	A	W1-6L	48	24								X		X X											REMOVE SIGN AND POSTS INSTALL A SET OF CHEVRONS AT THE SAME LOCATION			
		B A	W1-8 R W1-8 L	18 18	24 24		B-B	3.00 3.00								2 ~~1~~		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 174 FT SOUTH OF THE SIGNALIZED WEST HILL RD INTERSECTION	X X		
NB	MM 1.068, RT	C/D	D3-1	42	12		West Hill Rd	3.50					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY		9	
SB	MM 1.067, LT	F	R3-4	24	24								X		X											REMOVE SIGN AND POST			
		F	TOWN SIGN	18	12		NO U TURN						X													REMOVE SIGN			
NB	MM 1.026, RT	B	W1-8 R	18	24			3.00								1		X								INSTALLED NEW SIGN AND POST 69 FT NORTH OF WEATHREVANE ROAD INTERSECTION	X		
		A	W3-3	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 69 FT NORTH WEATHREVANE ROAD INTERSECTION 2 FT SOUTH OF NEW CHEVRON	X		
							SHEET SUBTOTALS	SF 45.50	SF	EA 9				EA 7		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 4

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 31 OF 78