STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 – KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 1.088, RT	D	RI-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 1.008, RT	C/D	D3-1	42	12		Weathervane Rd	3.50					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY		9	
NB	MM 1.105, RT	B A	WI-8 R WI-8 L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 63 FT SOUTH OF THE WEATHERVANE ROAD INTERSECTION	X X		
NB	MM 1.130, RT	B A	WI-8 R WI-8 L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 195 FT SOUTH OF THE WEATHERVANE ROAD INTERSECTION	X X		
NB	MM 1.152, RT	A	W3-3	36	36								X		X											REMOVE SIGN AND POST			
		A	W3-3P	24	18		SIGNAL AHEAD						X													REMOVE SIGN			
NB	MM 1.155, RT	B A	WI-8 R WI-8 L	18 18	24 24		B-B	3.00 3.00								2 +		X								INSTALLED BACK-TO-BACK ON A ~~SIGN BRACKET AND A SINGLE POST~~ 90 FT NORTH OF THE WEST HIIL RD SIGNALIZED INTERSECTION	X X		
NB	MM 1.163, RT	B	WI-8 R	18	24								X		X											REMOVE SIGN AND POST			
NB	MM 1.168, RT	B	WI-8 R	18	24								X		X											REMOVE SIGN AND POST			
NB	MM 1.174, RT	B	WI-8 R	18	24								X		X											REMOVE SIGN AND POST			
NB	MM 1.180, RT	B	WI-8 R	18	24			3.00								1		X								INSTALLED NEW SIGN AND POST 69 FT NORTH OF WEATHREVANE ROAD INTERSECTION	X		
		A	WI-6L	48	24								X		X X											REMOVE SIGN AND POSTS INSTALL NEW CUVRE LEFT SIGN AT THE SAME LOCATION			
		A	WI-2 L	30	30			6.25								+		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED LARGE ARROW SIGN	X		
NB	MM 1.244, RT	A	WI-2 L	30	30								X		X											REMOVE SIGN AND POST			
SB	MM 1.262, LT	F	WI-2Mq L	30	30			6.25								1		X								INSTALLED NEW SIGN AND POST 20 FT NORTH OF POLE# 86-4		13	
										EA	EA	EA	EA 9	EA	EA 9			FT 120										
							SHEET SUBTOTALS	SF 43.25	SF	EA 9				EA 9		EA 8		FT 120		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 5

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 32 OF 78