STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6 – KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL 3.00 lb/ft 7.60	TUBULAR STEEL 3.50 lb/ft 9.00	TUBULAR STEEL 4.00 lb/ft 10.80	TUBULAR STEEL 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.278, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 63 FT SOUTH OF AND ACROSS FROM POLE# 86-4	X		
NB	MM 1.299, RT	A/B	D3-1	48	12		South View Path	4.00					X		X	1		X								INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9	
		D	R1-1	30	30		STOP	6.25					X													INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 1.324, LT	E/F	D3-1	36	12		Bigelow Rd	3.00					X		X	1		X								INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9	
		H	R1-1	30	30		STOP	6.25					X													INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
SB	MM 1.377, LT	E/F	D3-1	48	12		Schoolhouse Rd	4.00					X		X	1		X								INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9	
		H	R1-1	30	30		STOP	6.25					X													INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 1.429, RT	F	~~W1-2Mg L~~	30	30		INCORRECT SIDE ROAD LAYOUT	6.25								1		X								INSTALLED NEW SIGN AND POST DIRECTLY ACROSS FROM POLE# 18/24/28		13	
SB	MM 1.513, LT	F	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 10 FT NORTH OF UTILITY POLE WITH FLASHING BEACON	X		
		F	W16-9P	24	12	F-Y-G	AHEAD	2.00																		INSTALL BENEATH PEDESTRIAN SYMBOL WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 1.515, LT	F	TOWN SIGN	30	30		CAUTION PEDESTRIANS AHEAD						X													REMOVE SIGN			
NB	MM 1.550, RT	A	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 639 FT SOUTH OF AND ACROSS FROM POLE# 18/24/28	X		
SB	MM 1.845, LT	F					EMPTY POST								X	–										REMOVE POST			
NB	MM 1.850, RT	A	R4-1	24	30		DO NOT PASS						X		X											REMOVE SIGN AND POST			
NB	MM 1.874, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 444 FT SOUTH OF DEAN HILL ROAD INTERSECTION	X		
										EA	EA	EA	EA 11	EA	EA 8		FT	FT 120	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 59.25	SF	EA 11				EA 8		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 6

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 33 OF 78