STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7 – KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER		MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.902, LT	F	W11-8	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 296 FT NORTH OF AND ACROSS FROM DEAN HILL ROAD INTERSECTION	X		
NB	MM 1.952, RT	A/B	D3-1	42	12			3.50					X		X	1		X								INSTALL NEW SIGN ABOVE STOP HERE ON RED SIGN WITH UPDATED DESIGN		9	
		D	TOWN SIGN	30	36		NOT IN FIELD						X													REMOVE SIGN			
		D	R10-6	24	36		NOT IN FIELD	6.00																			INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 1.964, RT	A/B	D3-1	42	12			3.50					X		X											REMOVE SIGN AND POST			
SB	MM 1.964, RT	E/F	D3-1	48	12			4.00					X		X	1		X								INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY		9	
SB	MM 2.021, LT	H	TOWN SIGN	30	36		NOT IN FIELD						X		X											REMOVE SIGN			
		H	R10-6	24	36		NOT IN FIELD	6.00								1		X									INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
SB	MM 2.037, LT	F	R4-1	24	30								X		X											REMOVE SIGN			
NB	MM 2.041, RT	H	TOWN SIGN	30	36								X		X											REMOVE SIGN			
		H	R10-6	24	36		NOT IN FIELD	6.00								1		X									INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X		
NB	MM 2.049, RT	A					EMPTY POST								X											REMOVE POST			
NB	MM 2.061, RT	A	W11-8	30	30			6.25								1		X									INSTALL NEW SIGN AND POST 1104 FT NORTH OF AND ACROSS FROM BUTLER ROAD INTERSECTION	X		
SB	MM 2.083, LT	F	R2-1	24	30			5.00					X		X	1		X								INSTALL NEW SIGN AND POST 987 FT NORTH OF BUTLER ROAD INTERSECTION	X		
NB	MM 1.952 RT	D	R1-1	30	30		NEW AOBE	6.25								0													
SB	MM 2.021 RT	H	R1-1	30	30		NEW AOBE	6.25																					
										EA	EA	EA	EA 9	EA	EA 9			FT	FT 120	FT			LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 46.50	SF				EA 9		EA 9	EA 7		FT 105		EA		LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
KILLINGTON TRAFFIC SIGN SUMMARY 7

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 34 OF 78