

# TRAFFIC SIGN SUMMARY SHEET 8 - KILLINGTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (In)			TUBULAR STEEL (In)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RE-INSTALL		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER	
																														lb/ft
SB	MM 2.270, LT	E/F	D3-1	30	12		<b>Butler Rd</b>	2.50															INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9					
		H	RI-1	30	30		<b>STOP</b>	6.25															INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X						
SB	MM 2.271, LT	E/F	D3-1	30	12		<b>Butler Rd</b>																REMOVE SIGN AND POST							
SB	MM 2.324, LT	F	R2-1	24	30		<b>SPEED LIMIT 35</b>	5.00															INSTALL NEW SIGN AND POST 285 FT SOUTH OF BUTLER ROAD	X						
		F	TOWN SIGN	24	12		<b>RADAR ENFORCED</b>																REMOVE SIGN							
NB	MM 2.423, RT	A	R4-3	24	30		<b>SLOWER TRAFFIC KEEP RIGHT</b>	5.00															INSTALL NEW SIGN AND POST 433 FT SOUTH OF RAVINE ROAD INTERSECTION	X						
NB	MM 2.503, RT	A/B	D3-1	36	12		<b>Ravine Rd</b>	3.00															INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9					
		D	RI-1	30	30		<b>STOP</b>	6.25															REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X						
		C	VR-017	24	30		<b>LEGAL LOAD LIMIT 16,000 POUNDS</b>																REMOVE SIGN							
NB	MM 2.507, RT	C	VR-017	24	30		<b>LEGAL LOAD LIMIT 16,000 POUNDS</b>	5.00															INSTALL NEW SIGN AND POST DIRECTLY ACROSS TOWN HIGHWAY FROM STOP SIGN		7					
NB	MM 2.561, RT	A	R2-1	24	30		<b>SPEED LIMIT 35</b>	5.00															INSTALL NEW SIGN AND POST DIRECTLY ACROSS FROM WEST PARK ROAD INTERSECTION	X						
SB	MM 2.565, LT	E/F	D3-1	42	12		<b>West Park Rd</b>	3.50															INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		9					
		H	RI-1	30	30		<b>STOP</b>	6.25															INSTALL NEW SIGN AND POST AT SAME LOCATION AS REMOVED SIGN ASSEMBLY	X						
SB	MM 2.565, LT	E/F	D3-1	42	12		<b>West Park Rd</b>																REMOVE SIGN AND POST							
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".</p>																														
<b>SHEET SUBTOTALS</b>								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								47.75		10	6	7	105		EA	LB														

PROJECT NAME: STATEWIDE SOUTHWEST REGION  
 PROJECT NUMBER: STP HRRR(7)  
 FILE NAME: IOKO22.DGN  
 PROJECT LEADER: N. AVERY  
 DESIGNED BY: N. AVERY  
 KILLINGTON TRAFFIC SIGN SUMMARY 8

PLOT DATE: 04-MAY-2010  
 DRAWN BY: N.AVERY  
 CHECKED BY: J. SCHULTZ  
 SHEET 35 OF 78