STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL 0/(In) FOUNDATION	TUBULAR STEEL 0/(In) 3.00 lb/ft 7.60	TUBULAR STEEL 0/(In) 3.50 lb/ft 9.00	TUBULAR STEEL 0/(In) 4.00 lb/ft 10.80	TUBULAR STEEL 0/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.007, LT	G/H	D3-1	42	12		N Pownal Rd	3.50					X													INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		10	
		F	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.030, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								REMOVE EXISTING SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
		A	R5-2	24	24		~~X~~ NOT IN FIELD						~~X~~													REMOVE SIGN			
SB	MM 0.080, LT	E/F	D3-1	36	12		Center St	3.00					X													INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		10	
		H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.088, LT	A/B	D3-1	36	12		Center St	3.00					X													INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		10	
		D	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 0.088, LT	G	W14-1	30	30		DEAD END	6.25					X		X	1		X								REMOVE EXISTING SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
		G	TOWN SIGN	18	24		~~SLOW CHILDREN~~ NOT IN FIELD						~~X~~													REMOVE SIGN			
NB	MM 0.0991, RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								INSTALL NEW SIGN AND POST 11 FT SOUTH OF POLE# 1/4/53 NEAR FENCE CORNER		7	
		A	R2-1	24	30		SPEED LIMIT 35	5.00																		INSTALL BENEATH LEGAL LOAD LIMIT AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.134, RT	A	W1-1 R	30	30			6.25								2		X								INSTALL NEW SIGN ON 2-POSTS 11 FT SOUTH OF POLE# 4/54/2	X		
		A	W6-060	30	30		HIDDEN DRIVES	6.25																		INSTALL BENEATH LEGAL LOAD LIMIT AT THE CORRECT SIGN HEIGHT		10	
SB	MM 0.149, LT	E	W1-6 R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 53 FT NORTH OF AND ACROSS FROM POLE# 4/54/2	X		
										EA	EA	EA	EA 10	EA	EA 5		FT	FT 150	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 70.00	SF	EA 10				EA 5		EA 10	FT 150			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
POWNAL TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 43 OF 78