STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.163, LT	F	WI-6 L	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 48 FT SOUTH OF POLE# 4/55/4CT/3/8-3>	X		
SB	MM 0.205, LT	F	WI-1 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 169 FT NORTH OF POLE# 4/55	X		
SB	MM 0.261, LT	H	RI-1	30	30			6.25								1		X								INSTALL SIGN AND POST 200 FT NORTH OF AND ACROSS FROM POLE #40T/46/2/8/5	X		
SB	MM 0.572, LT	F	W8-133	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 58 FT NORTH OF POLE# 46/14/16		10	
SB	MM 0.759, LT	F	R2-1	24	30			5.00								1		X								INSTALL NEW SIGN AND POST 1045 FT NORTH OF POLE# 46/14/16	X		
SB	MM 0.774, LT	E/F	D3-1	48	12			4.00					X													INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		10	
		H	RI-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.796, RT	A	W8-9	30	30								X													REMOVE SIGN			
		A	R2-1	24	30			5.00					X		X	1		X								INSTALL NEW SIGN AND POST 11FT NORTH OF POLE# 8/21/46/19	X		
SB	MM 0.938, LT	F	R2-1	24	30			5.00								1		X								INSTALL NEW SIGN AND POST 348 FT NORTH OF POLE# 46/20/22	X		
NB	MM 0.950, RT	A	WI-10 L	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 158 FT NORTH OF POLE# 8/21 THIS POLE IS OFF THE HIGHWAY IN A EASTERLY DIRECTION	X		
		A	W16-8P	42	8			2.33																		INSTALL BENEATH HORIZONTAL ALIGNMENT WARNING SIGN AT THE CORRECT SIGN HEIGHT		10	
NB	MM 0.997, RT	A/B	D3-1	42	6								X													REMOVE SIGN			
		D	RI-1	30	30			6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
NB	MM 0.997, RT	A/B	D3-1	60	12		INSTALLED 10' SOUTH OF POLE #46 23	5.00								2		X								INSTALL NEW SIGN ON 2-POSTS 2 FT NORTH OF STOP SIGN PARALLEL WITH TOWN HIGHWAY		10	

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60
			EA	EA	EA	EA 6	EA	EA 3		FT	FT 210	FT		LB	LB	LB	LB
SHEET SUBTOTALS	SF 74.58	SF	EA 6				EA 3		EA 14	FT 210			EA	LB			

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
POWNAL TRAFFIC SIGN SUMMARY 2

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 44 OF 78