STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - POWNAL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.999, RT	A	TOWN SIGN	24	18		NO TRUCKS						X		X											REMOVE SIGN AND POST			
NB	MM 1.012, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 79 FT NORTH OF POLE# 46/23	X		
NB	MM 1.032, LT	F	W1-10 R	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 158 FT NORTH OF POLE# 8/21 THIS POLE IS OFF THE HIGHWAY IN A EASTERLY DIRECTION	X		
		F	W16-8P	42	8		Carpenter Hill Rd	2.33																		INSTALL BENEATH HORIZONTAL ALIGNMENT WARNING SIGN AT THE CORRECT SIGN HEIGHT		10	
NB	MM 1.171, RT	A	W1-2 R	30	30		MISSING FROM FIELD						X		X											REMOVE SIGN AND POST			
		A	R2-5A	24	30		REDUCED SPEED AHEAD MISSING FROM FIELD						X													REMOVE SIGN			
NB	MM 1.206, RT	A	W1-1 R	30	30			6.25								2		X								INSTALL NEW SIGN ON 2-POSTS 1104 FT NORTH OF POLE# 46/23 ACCOUNT FOR SCHOOL BUS STOP SIGN AND 25 MPH PLAQUE	X		
		A	S3-1	30	30		SCHOOL BUS STOP AHEAD NOT IN FIELD	6.25					X		X											INSTALL BENEATH RIGHT TURN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
		A	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL PLAQUE ON RIGHT HAND POST BENEATH RIGHT TURN WARNING SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 1.234, LT	E	W1-8	18	24								X		X											REMOVE SIGN AND POST			
		E	W1-6	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 612 FT SOUTH OF THE CENTER OF DRIVE FOR HOUSE #1522 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
		F	W1-6	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 612 FT SOUTH OF THE CENTER OF DRIVE FOR HOUSE #1522 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
SB	MM 1.241, LT	E	W1-8	18	24								X		X											REMOVE SIGN AND POST			
SB	MM 1.246, LT	F	W1-8	18	24								X		X											REMOVE SIGN AND POST			
		E	W1-6	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 512 FT SOUTH OF THE CENTER OF DRIVE FOR HOUSE #1522 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
							SHEET SUBTOTALS	SF 55.08	SF				EA 7		EA 6	EA 11		FT 165			EA		LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
POWNAL TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 45 OF 78