STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 – RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) lb/ft 1.75 (1.88)	SQUARE STEEL (In) lb/ft 2.00 (2.42)	SQUARE STEEL (In) lb/ft 2.50 (3.35)	TUBULAR STEEL O/(In) lb/ft FOUNDATION	TUBULAR STEEL O/(In) lb/ft 3.00 (7.60)	TUBULAR STEEL O/(In) lb/ft 3.50 (9.00)	TUBULAR STEEL O/(In) lb/ft 4.00 (10.80)	TUBULAR STEEL O/(In) lb/ft 5.00 (14.60)	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.009, RT	A	VD-421	30	24		Welcome To VERMONT	5.00								1		X								INSTALL NEW SIGN AND POST ACROSS MONUMENT VT1937 RAS 13 AND 48 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT		11	
NB	MM 0.024, RT	A	TOWN SIGN	30	24		Vermont 153						X		X											REMOVE SIGN AND POST			
		A	VR-048	30	24		STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS						X													REMOVE SIGN AND POST			
NB	MM 0.047, RT	A	M3-1	24	12		NORTH	2.00								1		X								INSTALL NEW SIGN AND POST 248 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT	X		
		A	M1-6	30	24		153	5.00																		INSTALL BENEATH CARDINAL DIRECTIONAL SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.055, RT	A	VR-114M	36	48		STATE OF VERMONT SPEED LIMIT VITESSE MAXIMUM 50 UNLESS OTHERWISE POSTED RADAR ENFORCEMENT						X		X											REMOVE SIGN AND POST			
NB	MM 0.085, RT	A	R2-1	30	24		SPEED LIMIT 50	5.00								1		X								INSTALL NEW SIGN AND POST 449 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT	X		
		A	VR-208	24	24		UNLESS OTHERWISE POSTED	4.00																		INSTALL BENEATH SPEED LIMIT 50 SIGN AT THE CORRECT SIGN HEIGHT		11	
NB	MM 0.094, RT	A	TOWN SIGN	30	24		DON'T TRASH VERMONT						X		X											REMOVE SIGN AND POST			
		A	TOWN SIGN	30	24		SLOW CHILDREN PLAYING						X													REMOVE SIGN AND POST			
NB	MM 0.123, RT	A	VR-601	30	36		SAFETY BELTS REQUIRED	7.50								1		X								INSTALL NEW SIGN AND POST 649 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT		11	
NB	MM 0.161, RT	A	VR-048	30	24		STATE LAW STOP FOR SCHOOL BUS FLASHING RED LIGHTS	5.00								1		X								INSTALL NEW SIGN AND POST 850 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT		11	
NB	MM 0.199, RT	A	VR-203b	30	24		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS	5.00								1		X								INSTALL NEW SIGN AND POST 1051 FT NORTH OF NY-VT STATE LINE GRANITE MONUMENT		11	
							SHEET SUBTOTALS	SF 38.50	SF	EA 5				EA 3		EA 6	FT 90			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 52 OF 78