STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.134, RT	A/B	D3-1	30	12		East St	2.50																		INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		II	
		D	R2-1	30	30		STOP REMOVED EXISTING TO INSTALL NEW	6.25					X		X	1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
NB	MM 1.144, RT	A	TOWN SIGN	18	24		WATCH FOR CHILDREN						X		X											REMOVE SIGN AND POST			
NB	MM 1.145, RT	C	VR-345	24	30		NO PARKING HERE TO CORNER	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 74 FT NORTH OF EAST STREET INTERSECTION PARALLEL TO TOWN HIGHWAY 153		II	
SB	MM 1.185, LT	E/F	D3-1	30	12		Mill Rd	2.50																		INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		II	
		H	R1-1	30	30		STOP NOT IN FIELD	6.25					X		X	1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
NB	MM 1.189, RT	C	R1-1	30	30		STOP NOT IN FIELD						X		X											REMOVE SIGN AND POST			
SB	MM 1.192, LT	E/F	D3-1	24	8		Mill Rd						X		X											REMOVE SIGN AND POST			
NB	MM 1.210, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 111 FT NORTH OF POLE # 2/25T/5/99/159/380/L2	X		
NB	MM 1.246, LT	F	W11-2	30	30	F-Y-G		6.25								1		X								INSTALL NEW SIGN AND POST 10 FT SOUTH OF POLE# 103/384	X		
		F	W16-4P	30	24	F-Y-G	NEXT 800 FT	5.00								1		X								INSTALL BENEATH PEDESTRIAN SYMBOL SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 1.512, RT	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 21 FT SOUTH OF POLE# 364/83	X		
SB	MM 1.512, LT	F	R2-1	30	36		SPEED LIMIT 35	7.50								1		X								INSTALL NEW SIGN AND POST 21 FT SOUTH OF AND ACROSS FROM POLE# 364/83	X		
SB	MM 1.565, LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
SB	MM 1.578, LT	F	W3-5	36	36		SPEED LIMIT 35	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 190 FT SOUTH OF POLE# 362/80	X		
										EA	EA	EA	EA 9	EA	EA 9			FT	FT 150	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 60.25	SF	EA 9				EA 9		EA 10		FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 54 OF 78