STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.617, LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
SB	MM 1.693, LT	F	W1-2 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 417 FT NORTH OF POLE# 362/80	X		
NB	MM 1.862, RT	A	W1-4 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 10 FT SOUTH OF POLE# 156/355/69	X		
SB	MM 2.123, LT	F	W1-4 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 1368 FT NORTH OF AND ACROSS FROM POLE# 156/355/69	X		
SB	MM 2.161, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 1568 FT NORTH OF AND ACROSS FROM POLE# 156/355/69	X		
SB	MM 2.199, LT	E/F	D3-1	36	12		Hebron Rd	3.00																		INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
SB	MM 2.213, LT	E/F	D3-1	30	8		Hebron Rd						X		X											REMOVE SIGN AND POST			
		G	VD-700	6	10		0131 0210 0130						X													REMOVE SIGN			
SB	MM 2.275, RT	A	W1-4 R	30	30								X		X											REMOVE SIGN AND POST			
		A	W3-5	36	36		SPEED LIMIT 35	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 338 FT SOUTH OF POLE# 159/340	X		
NB	MM 2.342, RT	A	R2-1	30	36		SPEED LIMIT 35 MOVED 10' FROM UTILITY POLE (INFRONT)	7.50					X		X	1		X								INSTALL NEW SIGN AND POST 16 FT NORTH OF POLE# 159/340	X		
SB	MM 2.342, LT	F	R2-1	24	30		SPEED LIMIT 40	5.00								1		X								INSTALL NEW SIGN AND POST 16 FT NORTH OF AND ACROSS FROM POLE# 159/340	X		
SB	MM 2.351, LT	F	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE SIGN AND POST			
NB	MM 2.395, RT	A	W1-4 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 10 FT SOUTH OF POLE# 156/338	X		
										EA	EA	EA	EA 7	EA	EA 6		FT	FT 150	FT					LB	LB	LB	LB				
							SHEET SUBTOTALS	SF 60.75	SF	EA 7				EA 6		EA 10	FT 150			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 4

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 55 OF 78