STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5 – RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 2.442, RT	A	R2-1	30	36		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
			TOWN SIGN	24	30		SPEED ENFORCED BY RADAR						X													REMOVE SIGN			
NB	MM 2.503, RT	A	W11-8	30	30		ON UTILITY POLE						X		X											REMOVE SIGN AND POST			
NB	MM 2.596, RT	A	W11-8	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 42 FT SOUTH OF POLE# 5/27/159/330	X		
SB	MM 2.647, LT	F	W1-4 R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 227 FT NORTH OF AND ACROSS FROM POLE# 5/27/159/330	X		
SB	MM 2.709, LT	A	W1-4 R	30	30								X		X											REMOVE SIGN AND POST			
NB	MM 2.753, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 132 FT SOUTH OF AND ACROSS FROM POLE# 323/22	X		
SB	MM 2.778, LT	F	W11-8	30	30		ON UTILITY POLE						X		X											REMOVE SIGN AND POST			
SB	MM 2.780, LT	F	W11-8	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 10 FT NORTH OF POLE# 323/22	X		
SB	MM 3.173, LT	F	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
NB	MM 3.184, RT	A	W1-2 L	30	30		NOT IN FIELD						X		X											REMOVE SIGN AND POST			
NB	MM 3.210, RT	A	W1-2 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 127 FT NORTH OF AND ACROSS FROM POLE# 6	X		
SB	MM 3.390, LT	F	W1-2 R	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 10 FT NORTH OF POLE# 11/5/2	X		
nb	MM 3.435, RT	A	W1-2 R	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 238 FT NORTH OF AND ACROSS FROM POLE# 11/5/2	X		
SB	MM 3.502, LT	E	W1-6 R	48	24			8.00								2		X								INSTALL NEW SIGN ON 2-POSTS 500 FT SOUTH OF AND ACROSS FROM POLE# CV276/18 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
										EA	EA	EA	EA 10	EA	EA 9		FT	FT 135	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 50.50	SF	EA 10				EA 9		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 5

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 56 OF 78