STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7 - RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 5.413,RT	A/B	D3-1	48	12		Mc Kieghan Rd	4.00	NEW SIGN WAS INSTALLED ON OPPOSITE SIDE DUE TO A LARGE TREE OBSTRUCTING THE VIEW OF THE SIGN.																		INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		D	R1-1	30	30		STOP	6.25								1		X									INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
NB	MM 5.823,RT	F	VD-700	6	10		0131 0210 0285						X		X												REMOVE SIGN AND POST			
NB	MM 5.867, RT	A	W1-2 R	30	30			6.25								1		X									INSTALL NEW SIGN AND POST 913 FT NORTH OF AND ACROSS FROM POLE# 230/148	X		
SB	MM 5.914, LT	F	W1-6 L	48	24		ALSO AN 18X18 OBJECT MARKER REMOVED	8.00					X		X	2		X									INSTALL NEW SIGN ON 2-POSTS 1162 FT NORTH OF POLE# 230/148 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
SB	MM 5.923, LT	E	W1-6 R	48	24			8.00					X		X	2		X									INSTALL NEW SIGN ON 2-POSTS 1209 FT NORTH OF POLE# 230/148 AT RIGHT ANGLES TO APPROACHING TRAFFIC	X		
SB	MM 5.962, LT	F	W1-2 L	30	30			6.25								1		X									INSTALL NEW SIGN AND POST 1415 FT NORTH OF POLE# 230/148	X		
SB	MM 6.022, LT	E/F	D3-1	36	12		Quarry Rd	3.00								1		X									INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30		STOP	6.25								1		X									INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
SB	MM 6.041, LT	E/F	D3-1	30	8		Quarry Rd						X		X												REMOVE SIGN AND POST			
NB	MM 6.136, RT	A	W1-10 L	36	36			9.00								2		X									INSTALL NEW SIGNS ON 2-POSTS 808 FT SOUTH OF THE INTERSECTION OF LEWIS ROAD	X		
		A	W16-8P	30	8		Perkins Rd	1.67																			INSTALL BENEATH HORIZONTAL ALIGNMENT WARNING SIGN AT THE CORRECT SIGN HEIGHT		11	
NB	MM 6.177, RT	D	R1-1	30	30		STOP	6.25								1		X									INSTALL NEW SIGN AND POST ON LEFT SIDE OF TOWN HIGHWAY FOLLOW STATE STANDARD FOR INSTALLATION GUIDANCE	X		
NB	MM 6.202, RT	A/B	D3-1	36	12		Perkins Rd	3.00					X		X												INSTALL SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		D	R1-1	30	30		STOP	6.25								1		X									INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
							SHEET SUBTOTALS	SF 74.17	SF	EA 5			EA 5		EA 5	EA 13	FT 195			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 7

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 58 OF 78