STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8 - RUPERT

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 6.280, LT	F	W1-10 L	36	36			9.00								2		X								INSTALL NEW SIGNS ON 2-POSTS 2170 FT SOUTH OF POLE# 202/121	X		
		F	W16-8P	30	8			1.67																		INSTALL BENEATH HORIZONTAL ALIGNMENT WARNING SIGN AT THE CORRECT SIGN HEIGHT		11	
NB	MM 6.700, RT	A	W1-2 R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 428 FT SOUTH OF POLE# 119/200	X		
NB	MM 6.777, RT	A	W5-2	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 21 FT SOUTH OF AND ACROSS FROM POLE# 119/200	X		
SB	MM 6.787, LT	F	W1-2 L	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 32 FT NORTH OF POLE# 119/200	X		
SB	MM 6.828, LT	E	OM3-L	12	36		NOT IN FIELD	3.00					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION - SOUTHWEST CORNER OF BRIDGE ABUTMENT	X		
NB	MM 6.828, RT	A	OM3-R	12	36		NOT IN FIELD	3.00					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION - SOUTHEAST CORNER OF BRIDGE ABUTMENT	X		
SB	MM 6.838, LT	F	OM3-R	12	36		REPLACED 11-8-11 AS/PER PUNCH LIST NOT IN FIELD	3.00					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION - NORTHWEST CORNER OF BRIDGE ABUTMENT	X		
NB	MM 6.842, RT	B	OM3-L	12	36		NOT IN FIELD	3.00					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION - NORTHEAST CORNER OF BRIDGE ABUTMENT	X		
SB	MM 6.827, LT	E/F	D3-1	42	12			3.50					X		X											INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30			6.25								1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
SB	MM 6.787, LT	F	W5-2	36	36			9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 143 FT SOUTH OF POLE# 115/196	X		
NB	MM 6.933, RT	A	W1-2 L	30	30			6.25					X		X	1		X								INSTALL NEW SIGN AND POST 465 FT SOUTH OF AND ACROSS FROM POLE# 112/193	X		
		A	VD-700	6	10								X													REMOVE SIGN			
SB	MM 7.023, LT	F	W1-4 R	30	30			6.25								1		X								INSTALL NEW SIGN AND POST 10 FT NORTH OF POLE# 112/193	X		
										EA	EA	EA	EA 7	EA	EA 6		FT	FT 225	FT		LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 75.42	SF	EA 7				EA 6		EA 15	FT 225			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
RUPERT TRAFFIC SIGN SUMMARY 8

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 59 OF 78