STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.00, RT	C	VD-024	72	10	NOT IN FIELD	~~Sunderland | Arlington~~	5.00					X		X	2		X								INSTALL NEW SIGN AND POST 42 FT SOUTH OF AND ACROSS FROM POLE* 4-5/20/55		13	
NB	MM 0.001, RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 22 FT SOUTH OF AND ACROSS FROM POLE* 4-5/20/55 JUST NORTH OF NEW TOWN LINE SIGN	X		
NB	MM 0.002, RT	A	TOWN SIGN	30	36		TOWN SIGN						X		X											REMOVE SIGN AND POST			
SB	MM 0.010, LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		X								INSTALL NEW SIGN AND POST 10 FT NORTH OF POLE* 4-5/20/55	X		
NB	MM 0.015, RT	A	TOWN SIGN	36	42		~~WARNING COVERED BRIDGE MAXIMUM HEIGHT 8'-2"~~ NOT IN FIELD						X		X											REMOVE SIGN AND POST			
		A	W12-2	36	36		8'-2"	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 37 FT NORTH OF AND ACROSS FROM POLE* 4-5/20/55	X		
		A	W16-2P	24	18		1750 FEET	3.00																		INSTALL BENEATH BRIDGE CLEARANCE SYMBOL SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM ~~0.026, RT~~ 0.031RT	A	R2-1	24	30		SPEED LIMIT 35 CHANGED LOCATION DUE TO A LARGE TREE OBSTRUCTING VIEW.	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 37 FT SOUTH OF AND ACROSS FROM POLE* 21/56	X		
~~SB~~ NB	MM 0.049, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE EXISTING SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION			
~~SB~~ NB	MM 0.054, RT	A	TOWN SIGN	30	36		COVERED BRIDGE 8'-2" CLEARANCE						X		X			X								REMOVE SIGN AND POST			
		A	R12-1	24	30		~~WEIGHT LIMIT 12 TONS~~ NOT IN FIELD	5.00					X		X	1		X								INSTALL NEW SIGN AND POST 37 FT SOUTH OF AND ACROSS FROM POLE* 21/56	X		
NB	MM 0.054, LT	E/F	D3-1	42	12		Town Line Rd	3.50					X		X	1		X								INSTALL NEW SIGN AND POST 37 FT SOUTH OF AND ACROSS FROM POLE* 21/56		13	
NB	MM 0.56, LT	H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 0.062, LT	G	W14-2	30	30		NO OUTLET NOT IN FIELD	6.25								1		X								INSTALL NEW SIGN AND POST 50 FT WEST OF SUNDERLAND ROAD ON THE NORTH SIDE OF TOWN LINE ROAD	X		
							SHEET SUBTOTALS	SF 59.25	SF	EA 9			EA 9		EA 9	EA 12		FT 180			EA	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER: N. AVERY
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 1

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 62 OF 78