STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL 0/(In) FOUNDATION	TUBULAR STEEL 0/(In) 3.00 lb/ft 7.60	TUBULAR STEEL 0/(In) 3.50 lb/ft 9.00	TUBULAR STEEL 0/(In) 4.00 lb/ft 10.80	TUBULAR STEEL 0/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN BOOK)	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.0780, LT	F	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE SIGN AND POST			
		F	W3-5	36	36		SPEED LIMIT 25	9.00								2		X									INSTALL NEW SIGN ON 2-POSTS 21 FT SOUTH OF AND ACROSS FROM POLE# 2/58/23	X		
NB	MM 0.080, RT	A	W5-3	36	36		ONE LANE BRIDGE	9.00								2		X									INSTALL NEW SIGN ON 2-POSTS 10 FT SOUTH OF POLE# 2/58/23	X		
SB	MM 0.217, LT	E/F	D3-1	42	12		Chiselville Rd	3.50																			INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30		STOP	6.25					X		X	1		X									REMOVE SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
SB	MM 0.220, RT	A	W3-2A	36	36			9.00								2		X									INSTALL NEW SIGN ON 2-POSTS 21 FT SOUTH OF AND ACROSS FROM POLE# 2/58/23	X		
SB	MM 0.235, LT	E/F	VR-025	36	6		Chiselville Rd						X		X												REMOVE SIGN AND POST			
SB	MM 0.235, RT	G	W14-2	30	30		NO OUTLET	5.00								1		X									INSTALL NEW SIGN AND POST 50 FT WEST OF SUNDERLAND ROAD ON THE NORTH SIDE OF CHISEVILLE ROAD	X		
SB	MM 0.290, LTT	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X												REMOVE SIGN AND POST			
NB	MM ~~0.330~~ 0.340, RT	A	R1-2	36	36		YIELD MOVED 53' TOWARDS BRIDGE	3.89								1		X									INSTALL NEW SIGN AND POST 58 FT SOUTH OF POLE# 4-5/32	X		
		A	R1-2A	24	18		TO ONCOMING TRAFFIC	5.00																			INSTALL BENEATH YIELD SIGN AT THE CORRECT SIGN HEIGHT	X		
NB	MM 0.330, LT	E	W12-2	30	30		8'-2"						X		X												REMOVE SIGN AND POST			
		E	VW-730P	12	24		CAUTION						X														REMOVE SIGN PLAQUE			
NB	MM 0.341, RT	A					EMPTY POST								X												REMOVE SIGN			

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	EA	LB	LB	LB	LB
						6		6			135						
SHEET SUBTOTALS	SF 50.64	SF	EA 6				EA 6		EA 9	FT 135			EA	LB			

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 2

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 63 OF 78