STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.386, LT	F	W12-2	30	30		8'-2" REINSTALLED NEW SIGN	5.00					X		X			X								REMOVE SIGN AND POST			
		F	VW-730P	12	24		CAUTION						X														REMOVE SIGN PLAQUE			
SB	MM 0.402, LT	F	W12-2	30	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X												REMOVE SIGN AND POST			
SB	MM 0.424, LT	F	W12-2	30	30		WEIGHT LIMIT 12 TONS	5.00								1		X									INSTALL NEW SIGN AND POST ACROSS FROM POLE# 2/71/4-5-6/4-5/35	X		
NB	MM 0.435, RT	C	W14-2	30	30		NO OUTLET	6.25								1		X									INSTALL NEW SIGN AND POST 50 FT WEST OF SUNDERLAND ROAD ON THE NORTH SIDE OF CHISEVILLE ROAD	X		
NB	MM 0.0438, RT	G	D3-1	36	12		Hayden Rd	3.00					X		X	1		X									INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		D	R1-1	30	30		STOP	6.25																			INSTALL NEW SIGN ON STREET NAME SIGN POST, 49 FT NORTH OF POLE# 2/71/4-5-6/4-5/35	X		
NB	MM 0.445, RT	D	R1-1	30	30		STOP	6.25								1		X									INSTALL NEW SIGN AND POST ACROSS FROM POLE# 2/71A/35A	X		
SB	MM 0.454, LT	F	W1-2 R	30	30			6.25								1		X									INSTALL NEW SIGN AND POST 74 FT SOUTH OF AND ACROSS FROM POLE# 72/36	X		
SB	MM 0.493, LT	F	W5-3	36	36		ONE LANE BRIDGE	9.00								2		X									INSTALL NEW SIGN ON 2-POSTS 69 FT SOUTH OF AND ACROSS FROM POLE# 2/73/37	X		
SB	MM 0.501, LT	E/F	D3-1	66	12		Roaring Branch Rd Pvt	5.50					X		X	2		X									INSTALL NEW SIGN ON 2-POSTS 26 FT SOUTH OF AND ACROSS FROM POLE# 2/73/37		13	
SB	MM 0.583, LT	F	W1-2 R	30	30								X		X												REMOVE SIGN AND POST			
		F	W5-3	30	30		ONE LANE BRIDGE						X														REMOVE SIGN			
SB	MM 0.645, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		X									INSTALL NEW SIGN AND POST 290 FT SOUTH OF AND ACROSS FROM POLE# 2/80/25T/43	X		
							SHEET SUBTOTALS	SF 52.50	SF				EA 8		EA 6	EA 10		FT 150		EA		LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 3

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 64 OF 78