STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4 - SUNDERLAND

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.697, LT		D3-1	36	12		Wilcox Rd	2.50																		INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		13	
		H	R1-1	30	30		STOP	6.25								1		X								INSTALL NEW SIGN AND POST ON RIGHT SIDE OF TOWN HIGHWAY AS PER STANDARD	X		
SB	MM 0.704, LT	E/F	D3-1	24	6		Wilcox Rd						X		X											REMOVE SIGN AND POST			
NB	MM 0.731, RT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 11 FT SOUTH OF POLE# 81/44	X		
SB	MM 0.736, LT	F	W12-2	36	36		8'-2"	9.00								2		X								INSTALL NEW SIGN ON 2-POSTS 16 FT NORTH OF AND ACROSS FROM POLE# 81/44	X		
		F	W16-3AP	30	12		1/2 MILE	2.50																		INSTALL BENEATH BRIDGE CLEARANCE SYMBOL SIGN AT THE CORRECT SIGN HEIGHT	X		
SB	MM 0.816, LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 438 FT NORTH OF AND ACROSS FROM POLE# 81/44	X		
SB	MM 0.825, LT	G/H	D3-1	36	6		Sunderland Hill Rd						X													REMOVE SIGN			
		E/F	D3-1	30	12		Laver Rd	2.50					X													INSTALL NEW SIGN ABOVE STOP WITH UPDATED DESIGN		12	
		H	R1-1	30	30		STOP	6.25					X		X	1		X								REMOVE EXISTING SIGN AND POST INSTALL NEW SIGN AND POST AT SAME LOCATION	X		
		H	R2-1	24	30		SPEED LIMIT 35						X													REMOVE SIGN			
NB	MM 0.832, RT	C	D3-1	60	12		Sunderland Hill Rd	5.00								2		X								INSTALL NEW SIGN ON 2-POSTS DIRECTLY ACROSS FROM LAVER ROAD INTERSECTION WITH SUNDERLAND ROAD		13	
NB	MM 0.841, RT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		X								INSTALL NEW SIGN AND POST 48 FT NORTH OF LAVER ROAD INTERSECTION WITH SUNDERLAND ROAD	X		
NB	MM 0.996, RT	A/B	D3-1	72	12		Beaver Meadows Rd Pvt	6.00					X		X	2		X								INSTALL NEW SIGN ON 2-POSTS 25 FT NORTH OF BEAVER MEADOWS ROAD AT ORIGINAL SIGN LOCATION		12	
SB	MM 1.012, LT	F	TOWN SIGN	30	36		WARNING COVERED BRIDGE MAXIMUM HEIGHT 8 FT 2 IN. NOT IN FIELD						X		X											REMOVE SIGN AND POST			
NB	MM 1.179, RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE SIGN AND POST			
										EA	EA	EA	EA 8	EA	EA 5		FT	FT 165	FT					LB	LB	LB	LB					
							SHEET SUBTOTALS	SF 55.00	SF	EA 8				EA 5		EA 11	FT 165			EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(7)

FILE NAME: 10K022.DGN
PROJECT LEADER:
DESIGNED BY: N. AVERY
SUNDERLAND TRAFFIC SIGN SUMMARY 4

PLOT DATE: 04-MAY-2010
DRAWN BY: N.AVERY
CHECKED BY: J. SCHULTZ
SHEET 65 OF 78